

# Proposal 1100641

Roadway Rehabilitation

Date Generated: 12/17/2013 Sections: 1

Date Revised: Amendments: 0

Call Order: 001 Highway Number:

Items: 24 Counties: Socorro

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	404010	16,636.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0020	407000	324.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	407001	140.000	TON	FOG SEAL	
0040	414000	1,518,690.000	SYIN	COLD MILLING (ASPHALT)	
0050	424004	66,640.000	TON	WMA SP-IV COMPLETE	
0060	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0070	621000	1.000	LS	MOBILIZATION	
0080	701000	546.000	S.F.	PANEL SIGNS	
0090	701100	1,093.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0100	702000	950.000	S.F.	CONSTRUCTION SIGNING	
0110	702100	910.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0120	702110	28.000	EACH	PORTABLE SIGN SUPPORT	
0130	702525	309.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0140	702600	1.000	EACH	SEQUENTIAL ARROW DISPLAY	
0150	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0160	703100	48.000	EACH	ROAD DELINEATOR TYPE GUIDE	
0170	703400	288.000	EACH	1/10TH MILE DELINEATOR	
0180	704002	1,230,030.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0190	704099	718,080.000	L.F.	TEMPORARY STRIPING	
0200	704856	4,230.000	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE C	
0210	704858	106.000	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE G	
0220	704871	8,450.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PJ	
0230	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0240	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(24 Items)

# Proposal A301341

Bridge Rehabilitation

Date Generated: 12/17/2013 Sections: 2

Date Revised: Amendments: 0

Call Order: 002 Highway Number:

Items: 8 Counties: Bernalillo

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: BRIDGE</b>					
0010	533000	12.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0020	536001	3,598.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0030	621000	1.000	LS	MOBILIZATION	
<b>Section 0002: CONSTRUCTION ENGINEERING</b>					
0040	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0050	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0060	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0070	703300	20.000		EACH REFLECTIVE BARRIER DELINEATOR	
0080	704701	1,610.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
<b>(8 Items)</b>					

# Proposal 1100520

Roadway Rehabilitation

Date Generated: 12/17/2013 Sections: 1

Date Revised: Amendments: 0

Call Order: 003 Highway Number:

Items: 21 Counties: Hidalgo

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	404010	9,670.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0020	407000	204.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	407001	90.000	TON	FOG SEAL	
0040	414000	953,340.000	SYIN	COLD MILLING (ASPHALT)	
0050	424004	42,380.000	TON	WMA SP-IV COMPLETE	
0060	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0070	621000	1.000	LS	MOBILIZATION	
0080	701000	1,151.000	S.F.	PANEL SIGNS	
0090	701100	2,237.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0100	702000	950.000	S.F.	CONSTRUCTION SIGNING	
0110	702100	910.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0120	702110	28.000	EACH	PORTABLE SIGN SUPPORT	
0130	702525	309.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0140	702600	1.000	EACH	SEQUENTIAL ARROW DISPLAY	
0150	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0160	703400	180.000	EACH	1/10TH MILE DELINEATOR	
0170	704002	782,400.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0180	704099	446,000.000	L.F.	TEMPORARY STRIPING	
0190	704858	56.000	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE G	
0200	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0210	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(21 Items)

# Proposal 1100470

Roadway Reconstruction

Date Generated: 12/17/2013 Sections: 1

Date Revised: Amendments: 0

Call Order: 004 Highway Number:

Items: 116 Counties: Dona Ana

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	13,080.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	700.000	C.Y.	BORROW	
0040	203200	700.000	C.Y.	SUBEXCAVATION	
0050	207000	32,060.000	S.Y.	SUBGRADE PREPARATION	
0060	303000	10,560.000	TON	BASE COURSE	
0070	407000	21.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0080	408100	55.000	TON	PRIME COAT MATERIAL	
0090	414000	14,940.000	SYIN	COLD MILLING (ASPHALT)	
0100	417000	1,200.000	S.Y.	MISCELLANEOUS PAVING	
0110	423282	7,920.000	TON	HMA SP-III COMPLETE	
0120	423283	3,670.000	TON	HMA SP-IV COMPLETE	
0130	451080	3,160.000	S.Y.	CONCRETE PAVEMENT-8"	
0140	502030	195.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0150	502036	64.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0160	511000	65.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0170	540060	9,160.000	LB	REINFORCING BARS GRADE 60	
0180	570437	2,110.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0190	570449	160.000	L.F.	30" STORM DRAIN CULVERT PIPE	
0200	570461	920.000	L.F.	36" STORM DRAIN CULVERT PIPE	
0210	570467	420.000	L.F.	42" STORM DRAIN CULVERT PIPE	
0220	570473	150.000	L.F.	48" STORM DRAIN CULVERT PIPE	
0230	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0240	601110	29,600.000	S.Y.	REMOVAL OF SURFACING	
0250	601998	200.000	L.F.	REMOVAL AND DISPOSAL OF AC CONDUIT PIPE (SINGLE CONDUIT)	
0260	603250	23.000	EACH	DROP INLET PROTECTION TYPE I	
0270	603261	200.000	L.F.	MULCH SOCKS	
0280	603280	1.000	LS	SWPPP MANAGEMENT	
0290	604310	2,620.000	S.Y.	GEOGRID BASE REINFORCEMENT	
0300	606619	6,100.000	L.F.	RESETTING OF CONCRETE WALL	

			BARRIER
0310	606620	3,400.000	L.F. STATE FURNISHED CONCRETE WALL BARRIER
0320	608004	3,600.000	S.Y. CONCRETE SIDEWALK 4"
0330	608106	1,650.000	S.Y. DRIVE PAD 6"
0340	608404	1,800.000	S.Y. CONCRETE MEDIAN PAVEMENT 4" (COLORED AND PATTERNED)
0350	609200	500.000	L.F. HEADER CURB
0360	609424	8,200.000	L.F. CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"
0370	609478	4,400.000	L.F. CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"
0380	609488	1,700.000	L.F. CONCRETE VERTICAL CURB AND GUTTER TYPE D 8" X 18"
0390	609674	210.000	L.F. CONCRETE VALLEY GUTTER 8" X 24"
0400	617000	1.000	LS VIBRATION MONITORING
0410	617003	1.000	LS VIDEO TAPING
0420	618000	1.000	LS TRAFFIC CONTROL MANAGEMENT
0430	621000	1.000	LS MOBILIZATION
0440	623331	15.000	EACH CURB DROP INLET TYPE I-B, OVER 4'
0450	623332	1.000	EACH CURB DROP INLET TYPE II-B, OVER 4'
0460	662044	3.000	EACH MANHOLE TYPE C-8' DIAMETER OVER 10' TO 14' DEPTH
0470	662062	1.000	EACH MANHOLE TYPE E-4' DIAMETER OVER 6' TO 10' DEPTH
0480	662072	6.000	EACH MANHOLE TYPE E-6' DIAMETER OVER 6' TO 10' DEPTH
0490	662074	3.000	EACH MANHOLE TYPE E-6' DIAMETER OVER 10' TO 14' DEPTH
0500	663202	1.000	LS GAS SYSTEM
0510	663206	1.000	LS WATER SYSTEM
0520	663207	1.000	LS SEWER SYSTEM
0530	667300	920.000	S.F. MASONRY BLOCK WALL
0540	701000	300.000	S.F. PANEL SIGNS
0550	701100	500.000	L.F. STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS
0560	702000	1,544.000	S.F. CONSTRUCTION SIGNING
0570	702100	303.000	L.F. STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING
0580	702110	60.000	EACH PORTABLE SIGN SUPPORT
0590	702238	40.000	EACH BARRICADE, TYPE III-8'
0600	702525	304.000	EACH CHANNELIZATION DEVICES TYPE DRUM
0610	702600	2.000	EACH SEQUENTIAL ARROW DISPLAY
0620	702610	4.000	EACH PORTABLE CHANGEABLE MESSAGE

SIGN				
0630	704000	12,650.000	L.F. RETROREFLECTORIZED PAINTED MARKINGS 4"	
0640	704002	25,000.000	L.F. RETROREFLECTORIZED PAINTED MARKINGS 6"	
0650	704100	20,621.000	L.F. REMOVABLE MARKING TAPE	
0660	704101	65.000	EACH TEMPORARY WORD OR SYMBOL	
0670	704814	850.000	L.F. TYPE I RETROREFLECTIVE PREFORMED PAVEMENT STRIPE 24"	
0680	704817	6.000	EACH TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING RIGHT ARROW	
0690	704818	15.000	EACH TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING LEFT ARROW	
0700	704819	2.000	EACH TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING THRU ARROW	
0710	704820	4.000	EACH TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING WORD (ONLY)	
0720	704832	17.000	EACH TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING BIKE	
0730	706100	1.000	EACH SERVICE RISER (SIGNAL)	
0740	706230	1.000	EACH METER PEDESTAL (COMBINATION)	
0750	706350	1.000	LS POWER SERVICE INSTALLATION	\$10,000.00000
0760	706420	1.000	EACH LIGHTING CONTROL CABINET-TWO CIRCUIT	
0770	707010	1.000	EACH TYPE I STANDARD, 10'	
0780	707015	4.000	EACH TYPE I STANDARD, 15'	
0790	707330	2.000	EACH TYPE III STANDARD, 30' ARM	
0800	707335	2.000	EACH TYPE III STANDARD, 35' ARM	
0810	707535	30.000	EACH TYPE V STANDARD, 35'	
0820	709020	9,350.000	L.F. RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0830	709030	4,950.000	L.F. RIGID ELECTRICAL CONDUIT 3" (DIA.)	
0840	710000	10.000	EACH ELECTRICAL PULL BOX (STANDARD)	
0850	710010	8.000	EACH ELECTRICAL PULL BOX (LARGE)	
0860	711005	1,070.000	L.F. MULTI CONDUCTOR CABLE 5	
0870	711007	450.000	L.F. MULTI CONDUCTOR CABLE 7	
0880	711020	500.000	L.F. MULTI CONDUCTOR CABLE 20	
0890	711102	16,400.000	L.F. SINGLE CONDUCTOR 2	
0900	711106	750.000	L.F. SINGLE CONDUCTOR 6	
0910	711110	2,050.000	L.F. SINGLE CONDUCTOR 10	
0920	711506	1,520.000	L.F. COMMUNICATION CABLE 6 PAIR	
0930	712031	8.000	EACH 3 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
0940	712051	8.000	EACH 5 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	

0950 712202 8.000	EACH	PEDESTRIAN COUNTDOWN SIGNAL (LED)	
0960 712330 4.000	EACH	3 SECTION BACKPLATE	
0970 712350 4.000	EACH	5 SECTION BACKPLATE	
0980 713020 8.000	EACH	PUSH BUTTON STATION	
0990 713430 2.000	EACH	PHASE SELECTOR MODULE	
1000 713511 2.000	EACH	OPTICAL DETECTOR, 1 DIRECTION, 1 CHANNEL	
1010 713600 350.000	L.F.	OPTICAL DETECTOR CABLE	
1020 713700 4.000	EACH	OPTICAL EMITTER	
1030 713807 700.000	L.F.	VIDEO CABLE	
1040 713810 4.000	EACH	VIDEO CAMERA	
1050 714000 1.000	EACH	TRAFFIC ACTUATED CONTROLLER	
1060 714280 1.000	EACH	8 PHASE DOUBLE RING CONTROLLER CABINET	
1070 714650 1.000	LS	TRAFFIC MANAGEMENT SYSTEM	
1080 716025 34.000	EACH	ROADWAY LUMINAIRE TYPE 250 S	
1090 716301 4.000	EACH	INTERNALLY ILLUMINATED SIGN	
1100 720060 11.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
1110 720110 34.000	EACH	REMOVE AND RESET IMPACT ATTENUATOR UNIT	
1120 750000 1.000	LS	INTELLIGENT TRANSPORTATION SYSTEM	
1130 750060 13.000	EACH	ITS PULLBOX (33"X24"X24")	
1140 801000 1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
1150 802000 1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
1160 901000 1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(116 Items)

# Proposal 1100930

Safety

Date Generated: 12/17/2013 Sections: 2

Date Revised: Amendments: 0

Call Order: 005 Highway Number:

Items: 48 Counties: Dona Ana

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	207000	16,300.000	S.Y.	SUBGRADE PREPARATION	
0020	303000	5,800.000	TON	BASE COURSE	
0030	408100	31.000	TON	PRIME COAT MATERIAL	
0040	416000	2,750.000	S.Y.	MINOR PAVEMENT	
0050	502030	280.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0060	502042	14.000	L.F.	DRILLED SHAFT FOUNDATION 42" DIAMETER	
0070	502054	18.000	L.F.	DRILLED SHAFT FOUNDATION 54" DIAMETER	
0080	511060	11.000	C.Y.	STRUCTURAL CONCRETE, CLASS G	
0090	540060	9,236.000	LB	REINFORCING BARS GRADE 60	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0110	601110	2,600.000	S.Y.	REMOVAL OF SURFACING	
0120	603280	1.000	LS	SWPPP MANAGEMENT	
0130	606542	7,600.000	L.F.	CONCRETE WALL BARRIER 42"	
0140	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0150	621000	1.000	LS	MOBILIZATION	
0160	663049	1.000	LS	PRECONSTRUCTION UTILITY SURVEY	
0170	663870	45.000	L.F.	BORING AND JACKING	
0180	701015	1.000	EACH	PERMANENT CHANGEABLE MESSAGE SIGN	
0190	701342	1.000	EACH	OVERHEAD SIGN STRUCTURE, BUTTERFLY TYPE, 30-INCH	
0200	702000	610.000	S.F.	CONSTRUCTION SIGNING	
0210	702100	352.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0220	702110	44.000	EACH	PORTABLE SIGN SUPPORT	
0230	702238	2.000	EACH	BARRICADE, TYPE III-8'	
0240	702525	200.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0250	702600	2.000	EACH	SEQUENTIAL ARROW DISPLAY	
0260	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	



0270	704000	38,390.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0280	706350	1.000	LS	POWER SERVICE INSTALLATION	\$30,000.00000
0290	707741	28.000	EACH	TYPE V STANDARD, 35', 2 ARMS	
0300	709020	6,780.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0310	710000	11.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0320	711102	16,100.000	L.F.	SINGLE CONDUCTOR 2	
0330	711104	230.000	L.F.	SINGLE CONDUCTOR 4	
0340	716700	56.000	EACH	LUMINAIRE TYPE LED	
0350	720050	2.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
0360	750000	1.000	LS	INTELLIGENT TRANSPORTATION SYSTEM	
0370	750100	2.000	EACH	CLOSED CIRCUIT TELEVISION STSTEM (CCTV)	
0380	750110	2.000	EACH	CAMERA LOWERING DEVICE	
0390	750250	1.000	EACH	ITS CONCRETE POLE, 50 FT	
0400	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0410	802000	1.000	LS	POST CONSTRUCTION PLANS	\$1,500.00000
<b>Section 0002: BRIDGE</b>					
0420	511000	2.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0430	511500	5,003.000	S.F.	SPECIAL SURFACE FINISH	
0440	514042	633.000	L.F.	CONCRETE BARRIER RAILINGS 42"	
0450	532100	5,003.000	S.F.	PERMANENT ANTI-GRAFFITI PROTECTIVE COATING	
0460	533000	69.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0470	540060	320.000	LB	REINFORCING BARS GRADE 60	
0480	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	

**(48 Items)**

# Proposal 6100770

Lighting

Date Generated: 12/17/2013 Sections: 1  
 Date Revised: Amendments: 0  
 Call Order: 006 Highway Number:  
 Items: 16 Counties: Sandoval

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: LIGHTING</b>					
0010	502030	46.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0020	540060	1,145.000	LB	REINFORCING BARS GRADE 60	
0030	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0040	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0050	621000	1.000	LS	MOBILIZATION	
0060	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0070	706010	1.000		EACH SERVICE POLE (LIGHTING)	
0080	706110	1.000		EACH SERVICE RISER (LIGHTING)	
0090	706350	1.000	LS	POWER SERVICE INSTALLATION	\$10,000.00000
0100	706420	1.000	EACH	LIGHTING CONTROL CABINET-TWO CIRCUIT	
0110	707540	7.000		EACH TYPE V STANDARD, 40'	
0120	709020	1,110.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0130	710000	5.000		EACH ELECTRICAL PULL BOX (STANDARD)	
0140	711102	2,220.000	L.F.	SINGLE CONDUCTOR 2	
0150	716700	7.000		EACH LUMINAIRE TYPE LED	
0160	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	

**(16 Items)**

# Proposal 6100294

Stockpiling

Date Generated: 12/17/2013 Sections: 1

Date Revised: Amendments: 0

Call Order: 007 Highway Number:

Items: 7 Counties: District Wide #6

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	304600	17,000.000	TON	STOCKPILED BASE COURSE	
0020	304800	1.000	LS	BASE COURSE/SUBBASE TESTING BY THE CONTRACTOR	
0030	410305	4,700.000	TON	STOCKPILED SURFACE TREATMENT AGGREGATE 3/8"	
0040	410310	5,800.000	TON	STOCKPILED SURFACE TREATMENT AGGREGATE 1/2"	
0050	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0060	621000	1.000	LS	MOBILIZATION	
0070	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
<b>(7 Items)</b>					

# Proposal 6100297

Roadway Rehabilitation

Date Generated: 12/17/2013 Sections: 1

Date Revised: Amendments: 0

Call Order: 008 Highway Number:

Items: 4 Counties: District Wide #6

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	411000	1,158,971.000	LB	HOT POURED CRACK SEALING	
0020	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0030	621000	1.000	LS	MOBILIZATION	
0040	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
<b>(4 Items)</b>					

# Proposal M600333

Bridge Rehabilitation

Date Generated: 12/17/2013 Sections: 2  
Date Revised: Amendments: 0  
Call Order: 009 Highway Number:  
Items: 8 Counties: Sandoval Cibola

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0020	621000	1.000	LS	MOBILIZATION	
0030	702600	2.000	EACH	SEQUENTIAL ARROW DISPLAY	
0040	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0050	704700	1,500.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0060	704701	1,200.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
<b>Section 0002: BRIDGE</b>					
0070	535100	5,305.000	S.Y.	CONCRETE SURFACE TREATMENT	
0080	536001	5,305.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
<b>(8 Items)</b>					

# Proposal A300921

Bridge Rehabilitation

Date Generated: 12/17/2013 Sections: 2

Date Revised: Amendments: 0

Call Order: 010 Highway Number:

Items: 11 Counties: Bernalillo

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: BRIDGE</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	541405	1.000	LS	PREFAB PEDESTRIAN BRIDGE	
0030	546000	1.000	LS	RECOATING STRUCTURES	
0040	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0050	621000	1.000	LS	MOBILIZATION	
0060	632000	0.600	ACRE	CLASS A SEEDING	
<b>Section 0002: CONSTRUCTION SIGNING</b>					
0070	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0080	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0090	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0100	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0110	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
<b>(11 Items)</b>					