

Proposal A301260A

Roadway Reconstruction

Proposal information table

Date Generated: 01/21/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 64 Counties: Bernalillo

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203100	5,500.000	C.Y.	BORROW	
0020	203200	3,650.000	C.Y.	SUBEXCAVATION	
0030	203211	7,290.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0040	207000	72,850.000	S.Y.	SUBGRADE PREPARATION	
0050	303000	23,980.000	TON	BASE COURSE	
0060	403701	2,220.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0070	405000	6,150.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0080	407000	90.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0090	408100	140.000	TON	PRIME COAT MATERIAL	
0100	411000	2,090.000	LB	HOT Poured CRACK SEALING	
0110	414000	103,000.000	SYIN	COLD MILLING (ASPHALT)	
0120	424003	45,530.000	TON	WMA SP-III COMPLETE	
0130	450085	550.000	S.Y.	CONCRETE PAVEMENT-8 1/2"	
0140	511030	45.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0150	511500	30,840.000	S.F.	SPECIAL SURFACE FINISH	
0160	540060	2,660.000	LB	REINFORCING BARS GRADE 60	
0170	570024	460.000	L.F.	24" CULVERT PIPE	
0180	570025	2.000	EACH	24" CULVERT PIPE END SECTION	
0190	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0200	601110	72,850.000	S.Y.	REMOVAL OF SURFACING	
0210	602060	7,670.000	S.Y.	RIPRAP CLASS G	
0220	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0230	604001	7,670.000	S.Y.	GEOTEXTILE CLASS 1	
0240	606001	630.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0250	606051	9.000	EACH	END TREATMENT TL-3 END TERMINAL	
0260	606062	9.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0270	606542	1,520.000	L.F.	CONCRETE WALL BARRIER 42"	
0280	606610	13,550.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0290	606619	33,900.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0300	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0310	617000	1.000	LS	VIBRATION MONITORING	
0320	617002	1.000	LS	AERIAL PROGRESS PHOTOS	\$10,000.00000

0330	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0340	618011	1.000	LS	PUBLIC AWARENESS	\$50,000.00000
0350	621000	1.000	LS	MOBILIZATION	
0360	622001	1.000	EACH	FIELD LABORATORY, TYPE I	
0370	630100	7,070.000	L.F.	MULTIPLE GLARE SHIELDING	
0380	662400	5.000	EACH	MANHOLE ADJUSTMENT	
0390	664000	1.000	LS	LANDSCAPE, COMPLETE	
0400	701010	2,870.000	S.F.	EXTRUDED PANEL SIGNS	
0410	702610	15.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0420	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0430	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$50,000.00000
0440	703002	8.000	EACH	OBJECT MARKER TYPE 2	
0450	703400	10.000	EACH	1/10TH MILE DELINEATOR	
0460	704000	266,195.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0470	704701	94,010.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0480	704716	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING COMBINATION (THRU AND LEFT) ARROW	
0490	704717	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0500	704718	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0510	704720	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0520	704735	9.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
0530	704869	275.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG	
0540	707752	7.000	EACH	TYPE V STANDARD, 50', 2 ARMS	
0550	709020	150.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0560	711102	300.000	L.F.	SINGLE CONDUCTOR 2	
0570	716040	14.000	EACH	ROADWAY LUMINAIRE TYPE 400 S	
0580	720050	3.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
0590	720060	6.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0600	720110	9.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0610	721000	143,990.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0620	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0630	802000	1.000	LS	POST CONSTRUCTION PLANS	\$20,000.00000
0640	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(64 Items)

Proposal A301260B

Roadway Reconstruction

Proposal information table

Date Generated: 01/21/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 65 Counties: Bernalillo

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203100	1,400.000	C.Y.	BORROW	
0020	203200	3,650.000	C.Y.	SUBEXCAVATION	
0030	203211	7,290.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0040	207000	72,850.000	S.Y.	SUBGRADE PREPARATION	
0050	303000	23,980.000	TON	BASE COURSE	
0060	403701	680.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0070	405000	6,150.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0080	407000	11.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0090	414000	101,550.000	SYIN	COLD MILLING (ASPHALT)	
0100	416000	31,120.000	S.Y.	MINOR PAVEMENT	
0110	450085	1,120.000	S.Y.	CONCRETE PAVEMENT-8 1/2"	
0120	450120	72,850.000	S.Y.	CONCRETE PAVEMENT-12"	
0130	452000	108,780.000	L.F.	SEALING CONCRETE PAVEMENT JOINTS	
0140	455100	72,850.000	S.Y.	DIAMOND GROOVING OF PCCP	
0150	511030	45.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0160	511500	30,840.000	S.F.	SPECIAL SURFACE FINISH	
0170	540060	2,660.000	LB	REINFORCING BARS GRADE 60	
0180	570024	460.000	L.F.	24" CULVERT PIPE	
0190	570025	2.000	EACH	24" CULVERT PIPE END SECTION	
0200	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0210	601110	73,880.000	S.Y.	REMOVAL OF SURFACING	
0220	602060	7,670.000	S.Y.	RIPRAP CLASS G	
0230	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0240	604001	7,670.000	S.Y.	GEOTEXTILE CLASS 1	
0250	606001	630.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0260	606051	9.000	EACH	END TREATMENT TL-3 END TERMINAL	
0270	606062	9.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0280	606542	1,520.000	L.F.	CONCRETE WALL BARRIER 42"	
0290	606610	13,550.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0300	606619	33,900.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0310	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0320	617000	1.000	LS	VIBRATION MONITORING	

0330	617002	1.000	LS	AERIAL PROGRESS PHOTOS	\$10,000.00000
0340	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0350	618011	1.000	LS	PUBLIC AWARENESS	\$50,000.00000
0360	621000	1.000	LS	MOBILIZATION	
0370	622001	1.000	EACH	FIELD LABORATORY, TYPE I	
0380	630100	7,070.000	L.F.	MULTIPLE GLARE SHIELDING	
0390	662400	5.000	EACH	MANHOLE ADJUSTMENT	
0400	664000	1.000	LS	LANDSCAPE, COMPLETE	
0410	701010	2,870.000	S.F.	EXTRUDED PANEL SIGNS	
0420	702610	15.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0430	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0440	702850	1.000	ALLOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$50,000.00000
0450	703002	8.000	EACH	OBJECT MARKER TYPE 2	
0460	703400	10.000	EACH	1/10TH MILE DELINEATOR	
0470	704000	315,095.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0480	704701	94,010.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0490	704716	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING COMBINATION (THRU AND LEFT) ARROW	
0500	704717	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0510	704718	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0520	704720	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0530	704735	9.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
0540	704869	275.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG	
0550	707752	7.000	EACH	TYPE V STANDARD, 50', 2 ARMS	
0560	709020	150.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0570	711102	300.000	L.F.	SINGLE CONDUCTOR 2	
0580	716040	14.000	EACH	ROADWAY LUMINAIRE TYPE 400 S	
0590	720050	3.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
0600	720060	6.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0610	720110	9.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0620	721000	143,990.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0630	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0640	802000	1.000	LS	POST CONSTRUCTION PLANS	\$20,000.00000
0650	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(65 Items)

Proposal S100140

Roadway Reconstruction

Proposal information table

Date Generated: 01/21/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 191 Counties: Santa Fe

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	96,700.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	25,400.000	C.Y.	BORROW	
0040	203200	2,500.000	C.Y.	SUBEXCAVATION	
0050	204002	1.000	ALOW	PRAIRIE DOG MANAGEMENT	\$5,000.00000
0060	207000	144,900.000	S.Y.	SUBGRADE PREPARATION	
0070	210000	7,590.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0080	213000	1.250	MILE	OBLITERATING OLD ROAD	
0090	303000	46,830.000	TON	BASE COURSE	
0100	403701	970.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0110	405000	15,300.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0120	407000	234.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0130	408100	244.000	TON	PRIME COAT MATERIAL	
0140	414000	56,380.000	SYIN	COLD MILLING (ASPHALT)	
0150	417000	8,100.000	S.Y.	MISCELLANEOUS PAVING	
0160	423282	44,530.000	TON	HMA SP-III COMPLETE	
0170	502036	48.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0180	502042	30.000	L.F.	DRILLED SHAFT FOUNDATION 42" DIAMETER	
0190	511000	192.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0200	511200	40.000	S.Y.	STRUCTURAL CONCRETE, CLASS A-4"	
0210	511300	312.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
0220	515000	41.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0230	540060	71,810.000	LB	REINFORCING BARS GRADE 60	
0240	541200	3,100.000	LB	STRUCTURAL STEEL FOR MISCELLANEOUS STRUCTURES	
0250	543100	80.000	L.F.	METAL RAILING, PEDESTRIAN	
0260	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0270	570437	4,628.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0280	570441	41.000	EACH	24" STORM DRAIN CULVERT PIPE END SECTION	
0290	570449	34.000	L.F.	30" STORM DRAIN CULVERT PIPE	
0300	570453	1.000	EACH	30" STORM DRAIN CULVERT PIPE END SECTION	
0310	570461	55.000	L.F.	36" STORM DRAIN CULVERT PIPE	
0320	570465	1.000	EACH	36" STORM DRAIN CULVERT PIPE END SECTION	

0330	570467	45.000	L.F.	42" STORM DRAIN CULVERT PIPE	
0340	570473	269.000	L.F.	48" STORM DRAIN CULVERT PIPE	
0350	570477	1.000	EACH	48" STORM DRAIN CULVERT PIPE END SECTION	
0360	570629	124.000	L.F.	40"X28"R STORM DRAIN CPA	
0370	571299	661.500	L.F.	14'11"S X 12'2"R STRUCTURAL PLATE PIPE ARCH	
0380	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0390	601110	104,600.000	S.Y.	REMOVAL OF SURFACING	
0400	602000	163.000	C.Y.	RIPRAP CLASS A	
0410	602060	1,960.000	S.Y.	RIPRAP CLASS G	
0420	603100	40.000	ACRE	TEMPORARY SOIL STABILANT	
0430	603221	200.000	L.F.	CHECK DAM TYPE II	
0440	603250	57.000	EACH	DROP INLET PROTECTION TYPE I	
0450	603260	620.000	S.Y.	CULVERT PROTECTION	
0460	603262	57,000.000	L.F.	COMPOSTED MULCH SOCKS	
0470	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0480	606001	7,662.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0490	606002	30.000	L.F.	DOUBLE FACED W-BEAM GUARDRAIL	
0500	606051	9.000	EACH	END TREATMENT TL-3 END TERMINAL	
0510	606053	8.000	EACH	END TREATMENT W-BEAM END ANCHOR	
0520	606055	1.000	EACH	END TREATMENT DRIVEWAY END ANCHOR	
0530	606060	110.000	L.F.	MEDIAN PROTECTION SYSTEM	
0540	606062	14.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0550	606063	1.000	EACH	EXISTING BEAM GUARDRAIL TO 31" BEAM GUARDRAIL TRANSITION	
0560	606542	2,200.000	L.F.	CONCRETE WALL BARRIER 42"	
0570	606600	2,099.000	L.F.	TEMPORARY CWB RETAINED BY THE DEPARTMENT	
0580	606619	2,000.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0590	606620	10,380.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0600	607026	13,120.000	L.F.	CHAIN LINK FENCE 6'	
0610	607066	7,190.000	L.F.	VINYL COATED CHAIN LINK FENCE 6'	
0620	607412	2.000	EACH	CHAIN LINK GATE, 12' (SPAN)	
0630	608004	1,780.000	S.Y.	CONCRETE SIDEWALK 4"	
0640	608204	150.000	S.Y.	CONCRETE MEDIAN PAVEMENT 4"	
0650	609324	6,300.000	L.F.	CONCRETE SLOPED CURB AND GUTTER 6" X 24"	
0660	609424	11,660.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	
0670	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0680	617003	1.000	LS	VIDEO TAPING	
0690	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0700	618011	1.000	LS	PUBLIC AWARENESS	\$10,000.00000
0710	621000	1.000	LS	MOBILIZATION	
0720	623094	1.000	EACH	MEDIAN DROP INLET 10'X5' (RURAL) H=3'1" TO 6'0"	
0730	623105	10.000	EACH	MEDIAN DROP INLET 5'X5' (URBAN) H=3'1" TO 6'0"	
0740	623106	1.000	EACH	MEDIAN DROP INLET 5'X5' (URBAN) H=6'1" TO 9'0"	

0750	623114	6.000	EACH	MEDIAN DROP INLET 5'X5' (RURAL) H=3'1" TO 6'0"	
0760	623301	9.000	EACH	CURB DROP INLET TYPE I-A, 0' TO 4'	
0770	623311	7.000	EACH	CURB DROP INLET TYPE I-B, 0' TO 4'	
0780	623321	3.000	EACH	CURB DROP INLET TYPE I-A, OVER 4'	
0790	623331	4.000	EACH	CURB DROP INLET TYPE I-B, OVER 4'	
0800	623332	1.000	EACH	CURB DROP INLET TYPE II-B, OVER 4'	
0810	623401	6.000	EACH	DROP INLET 4'X4'(TYPE I) H=4'-0"	
0820	623411	1.000	EACH	DROP INLET TYPE I, OVER 4'	
0830	631000	15,200.000	L.F.	RUMBLE STRIPS	
0840	632000	33.000	ACRE	CLASS A SEEDING	
0850	632020	1.000	ACRE	CLASS C SEEDING	
0860	662000	4.000	EACH	MANHOLE TYPE C-4' DIAMETER 0' TO 6' DEPTH	
0870	662002	3.000	EACH	MANHOLE TYPE C-4' DIAMETER OVER 6' TO 10' DEPTH	
0880	662010	7.000	EACH	MANHOLE TYPE C-6' DIAMETER 0' TO 6' DEPTH	
0890	662022	4.000	EACH	MANHOLE TYPE C-6' DIAMETER OVER 6' TO 10' DEPTH	
0900	690001	1.000	ALOW	RAILWAY FLAGGING	\$75,000.00000
0910	701000	1,050.000	S.F.	PANEL SIGNS	
0920	701010	200.000	S.F.	EXTRUDED PANEL SIGNS	
0930	701031	1.000	EACH	REMOVE AND RESET TRAFFIC SIGN	
0940	701100	1,650.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0950	701108	250.000	L.F.	STEEL I-BEAM POST TY S4X7.7	
0960	701208	12.000	EACH	BREAKAWAY BASE SYSTEM FOR STEEL I BEAM POST S4X7.7	
0970	701430	1.000	EACH	OVERHEAD SIGN STRUCTURE, CANTILEVER TYPE, 18-INCH	
0980	702000	4,300.000	S.F.	CONSTRUCTION SIGNING	
0990	702100	8,000.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
1000	702110	50.000	EACH	PORTABLE SIGN SUPPORT	
1010	702238	20.000	EACH	BARRICADE, TYPE III-8'	
1020	702525	570.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
1030	702600	6.000	EACH	SEQUENTIAL ARROW DISPLAY	
1040	702610	6.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
1050	702700	1.000	LS	TEMPORARY SIGNAL SPAN	
1060	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$32,600.00000
1070	704000	162,450.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
1080	704002	53,550.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
1090	704099	140,604.000	L.F.	TEMPORARY STRIPING	
1100	704700	54,800.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
1110	704718	3.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
1120	704719	11.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING THRU ARROW	

1130	704732	47.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING BIKE SYMBOL (BIKEWAY)	
1140	704735	4.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
1150	704770	2.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING WORD (ONLY)	
1160	704776	4.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING WORD YIELD)	
1170	704869	555.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG	
1180	704876	250.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
1190	704877	250.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TH	
1200	705000	1.000	ALOW	SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$10,000.00000
1210	706100	1.000	EACH	SERVICE RISER (SIGNAL)	
1220	706210	2.000	EACH	METER PEDESTAL (LIGHTING)	
1230	706230	3.000	EACH	METER PEDESTAL (COMBINATION)	
1240	706350	1.000	LS	POWER SERVICE INSTALLATION	\$30,000.00000
1250	706405	2.000	EACH	LIGHTING CONTROL CABINET-SIX CIRCUIT	
1260	707004	3.000	EACH	TYPE I STANDARD, 4'	
1270	707010	6.000	EACH	TYPE I STANDARD, 10'	
1280	707330	1.000	EACH	TYPE III STANDARD, 30' ARM	
1290	707335	2.000	EACH	TYPE III STANDARD, 35' ARM	
1300	707350	1.000	EACH	TYPE III STANDARD, 50' ARM	
1310	707525	8.000	EACH	TYPE V STANDARD, 25'	
1320	707540	111.000	EACH	TYPE V STANDARD, 40'	
1330	709007	700.000	L.F.	RIGID ELECTRICAL CONDUIT 3/4" (DIA.)	
1340	709020	26,810.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
1350	709030	18,900.000	L.F.	RIGID ELECTRICAL CONDUIT 3" (DIA.)	
1360	709040	800.000	L.F.	RIGID ELECTRICAL CONDUIT 4" (DIA.)	
1370	710000	28.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
1380	710010	23.000	EACH	ELECTRICAL PULL BOX (LARGE)	
1390	711003	700.000	L.F.	MULTI CONDUCTOR-CABLE 3	
1400	711005	3,600.000	L.F.	MULTI CONDUCTOR CABLE 5	
1410	711020	1,650.000	L.F.	MULTI CONDUCTOR CABLE 20	
1420	711101	51,000.000	L.F.	SINGLE CONDUCTOR 1	
1430	711102	5,350.000	L.F.	SINGLE CONDUCTOR 2	
1440	711106	1,100.000	L.F.	SINGLE CONDUCTOR 6	
1450	711108	1,750.000	L.F.	SINGLE CONDUCTOR 8	
1460	711512	6,440.000	L.F.	COMMUNICATION CABLE 12 PAIR	
1470	712031	13.000	EACH	3 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
1480	712201	8.000	EACH	PEDESTRIAN SIGNAL (LED)	
1490	712330	9.000	EACH	3 SECTION BACKPLATE	
1500	713020	8.000	EACH	PUSH BUTTON STATION	
1510	713030	8,130.000	L.F.	LOOP DETECTOR WIRE	

1520	713250	20,000.000	L.F.	LOOP LEAD-IN CABLE	
1530	713300	2,930.000	L.F.	DETECTOR SAW CUT	
1540	713430	3.000	EACH	PHASE SELECTOR MODULE	
1550	713511	4.000	EACH	OPTICAL DETECTOR, 1 DIRECTION, 1 CHANNEL	
1560	713600	850.000	L.F.	OPTICAL DETECTOR CABLE	
1570	714000	3.000	EACH	TRAFFIC ACTUATED CONTROLLER	
1580	714280	3.000	EACH	8 PHASE DOUBLE RING CONTROLLER CABINET	
1590	714300	1.000	LS	CLOSED LOOP TRAFFIC CONTROL SYSTEM	
1600	716700	135.000	EACH	LUMINAIRE TYPE LED	
1610	720050	2.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
1620	720060	15.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
1630	720110	10.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
1640	721000	151,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
1650	750000	1.000	LS	INTELLIGENT TRANSPORTATION SYSTEM	
1660	750060	55.000	EACH	ITS PULLBOX (33"X24"X24")	
1670	750080	7.000	EACH	ITS MANHOLE (48"X48"X48")	
1680	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
1690	802000	1.000	LS	POST CONSTRUCTION PLANS	\$8,000.00000
1700	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

Section 0002: BRIDGE

1710	210000	18,143.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
1720	501353	180.000	L.F.	OBSTRUCTION REMOVAL	
1730	502048	896.000	L.F.	DRILLED SHAFT FOUNDATION 48" DIAMETER	
1740	502066	400.000	L.F.	DRILLED SHAFT FOUNDATION 66" DIAMETER	
1750	505000	112.000	EACH	CROSSHOLE SONIC LOGGING CONSULTANT TESTING	
1760	511300	812.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
1770	511601	1.000	LS	WIND BREAK	
1780	511602	1.000	LS	FOGGING SYSTEM	
1790	512003	1,884.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
1800	512006	40.000	C.Y.	SPECIAL CONCRETE	
1810	514042	2,099.000	L.F.	CONCRETE BARRIER RAILINGS 42"	
1820	516000	282.000	C.Y.	FLOWABLE FILL	
1830	518072	3,151.000	L.F.	PRESTRESSED CONCRETE BRIDGE MEMBER TYPE 72	
1840	531001	47,991.000	S.F.	PERMANENT ANTI-GRAFFITI PROTECTIVE COATING	
1850	540060	233,762.000	LB	REINFORCING BARS GRADE 60	
1860	540160	405,713.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
1870	541000	33,422.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
1880	562000	319.000	L.F.	BRIDGE JOINT STRIP SEAL	
1890	564000	383.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
1900	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	

1910 667003 1.000

LS

ARTWORK COMPLETE

(191 Items)

Proposal 4101090

Fencing

Proposal information table

Date Generated: 01/21/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 004 Highway Number:
Items: 15 Counties: Colfax

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	511000	4.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0020	540060	119.000	LB	REINFORCING BARS GRADE 60	
0030	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0040	607012	47,634.000	L.F.	GAME FENCE	
0050	607013	24.000	EACH	GAME ESCAPE RAMP	
0060	607455	2.000	EACH	CHAIN LINK GATE, 8' S X 8' R	
0070	610080	355.000	L.F.	GAME GUARD	
0080	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0090	621000	1.000	LS	MOBILIZATION	
0100	701000	112.000	S.F.	PANEL SIGNS	
0120	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0130	707018	7.000	EACH	TYPE I STANDARD, 18'	
0140	712011	14.000	EACH	1 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
0150	715110	14.000	EACH	FLASHER CONTROLLER WITH TIME CLOCK	
0160	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	

(15 Items)

Proposal 1100830

Bridge Rehabilitation

Proposal information table

Date Generated: 01/21/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 005 Highway Number:
Items: 108 Counties: Dona Ana

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203000	1,140.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	203110	10.000	TON	BORROW	
0030	207000	29,580.000	S.Y.	SUBGRADE PREPARATION	
0040	303000	8,560.000	TON	BASE COURSE	
0050	404010	6,050.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0060	405000	4,000.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0070	407000	25.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0080	408100	51.000	TON	PRIME COAT MATERIAL	
0090	423282	11,890.000	TON	HMA SP-III COMPLETE	
0100	451080	910.000	S.Y.	CONCRETE PAVEMENT-8"	
0110	502030	72.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0120	502042	14.000	L.F.	DRILLED SHAFT FOUNDATION 42" DIAMETER	
0130	515000	14.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0140	540060	1,793.000	LB	REINFORCING BARS GRADE 60	
0150	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0160	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0170	601110	25,290.000	S.Y.	REMOVAL OF SURFACING	
0180	602000	4.000	C.Y.	RIPRAP CLASS A	
0190	602060	43.000	S.Y.	RIPRAP CLASS G	
0200	603050	1.000	ALOW	CLEAN WATER ACT COMPLIANCE WORK PLAN	\$5,000.00000
0210	603262	5,643.000	L.F.	COMPOSTED MULCH SOCKS	
0220	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0230	606001	3,462.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0240	606051	8.000	EACH	END TREATMENT TL-3 END TERMINAL	
0250	606053	4.000	EACH	END TREATMENT W-BEAM END ANCHOR	
0260	606062	12.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0270	606499	3,200.000	L.F.	POST AND CABLE BARRIER	
0280	606610	8,150.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0290	606619	8,150.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0300	607026	220.000	L.F.	CHAIN LINK FENCE 6'	
0310	608004	400.000	S.Y.	CONCRETE SIDEWALK 4"	
0320	608106	5.000	S.Y.	DRIVE PAD 6"	

0330	609374	1,429.000	L.F.	CONCRETE SLOPED CURB AND GUTTER 8" X 24"	
0340	609444	455.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 8" X 24"	
0350	609478	872.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	
0360	609706	20.000	L.F.	CONCRETE LAYDOWN CURB 6"	
0370	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0380	621000	1.000	LS	MOBILIZATION	
0390	630100	8,000.000	L.F.	MULTIPLE GLARE SHIELDING	
0400	631000	2,990.000	L.F.	RUMBLE STRIPS	
0410	632000	4.000	ACRE	CLASS A SEEDING	
0420	632020	2.000	ACRE	CLASS C SEEDING	
0430	663049	1.000	LS	PRECONSTRUCTION UTILITY SURVEY	
0440	702000	2,181.000	S.F.	CONSTRUCTION SIGNING	
0450	702100	1,998.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0460	702110	48.000	EACH	PORTABLE SIGN SUPPORT	
0470	702238	23.000	EACH	BARRICADE, TYPE III-8'	
0480	702525	411.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0490	702600	3.000	EACH	SEQUENTIAL ARROW DISPLAY	
0500	702610	7.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0510	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$30,600.00000
0520	703400	40.000	EACH	1/10TH MILE DELINEATOR	
0530	704000	21,966.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0540	704002	119,061.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0550	704099	65,627.000	L.F.	TEMPORARY STRIPING	
0560	704100	16,029.000	L.F.	REMOVABLE MARKING TAPE	
0570	704101	8.000	EACH	TEMPORARY WORD OR SYMBOL	
0580	704762	5,250.000	L.F.	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT STRIPE 12"	
0590	704764	450.000	L.F.	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT STRIPE 24"	
0600	704767	2.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING RIGHT A ROW	
0610	704768	6.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING LEFT AR ROW	
0620	704770	4.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING WORD (ONLY)	
0630	704785	3.000	EACH	RETROREFLECTIVE PREFORMED PATTERNED PAVEMENT MARKING RIGHT LANE DROP ARROW	
0640	704857	64.000	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE D	
0650	704858	55.000	EACH	REFLECTIVE RAISED PAVEMENT MARKER TYPE G	
0660	705000	1.000	ALOW	SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$1,000.00000
0670	706100	1.000	EACH	SERVICE RISER (SIGNAL)	
0680	706200	1.000	EACH	METER PEDESTAL (SIGNAL)	
0690	706210	1.000	EACH	METER PEDESTAL (LIGHTING)	

0700	706350	1.000	LS	POWER SERVICE INSTALLATION	\$20,000.00000
0710	706405	1.000	EACH	LIGHTING CONTROL CABINET-SIX CIRCUIT	
0720	707540	19.000	EACH	TYPE V STANDARD, 40'	
0730	709020	3,280.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0740	710000	13.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0750	711102	8,100.000	L.F.	SINGLE CONDUCTOR 2	
0760	716700	19.000	EACH	LUMINAIRE TYPE LED	
0770	720060	3.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0780	721000	75,170.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0790	750000	1.000	LS	INTELLIGENT TRANSPORTATION SYSTEM	
0800	750100	2.000	EACH	CLOSED CIRCUIT TELEVISION STSTEM (CCTV)	
0810	750110	2.000	EACH	CAMERA LOWERING DEVICE	
0820	750265	1.000	EACH	ITS CONCRETE POLE, 65 FT	
0830	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0840	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
0850	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

Section 0002: BRIDGE

0860	210000	132.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0870	511200	329.000	S.Y.	STRUCTURAL CONCRETE, CLASS A-4"	
0880	511300	278.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
0890	511500	29,520.000	S.F.	SPECIAL SURFACE FINISH	
0900	511600	2,604.000	S.F.	WATERPROOFING	
0910	511601	1.000	LS	WIND BREAK	
0920	511602	1.000	LS	FOGGING SYSTEM	
0930	512003	2,079.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0940	514042	1,716.000	L.F.	CONCRETE BARRIER RAILINGS 42"	
0950	515000	71.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0960	516000	2,044.000	C.Y.	FLOWABLE FILL	
0970	518045	2,087.000	L.F.	PRESTRESSED CONCRETE BRIDGE MEMBER TYPE 45	
0980	518054	1,890.000	L.F.	PRESTRESSED CONCRETE BRIDGE MEMBER TYPE 54	
0990	531001	18,770.000	S.F.	PERMANENT ANTI-GRAFFITI PROTECTIVE COATING	
1000	533000	81.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
1010	540060	61,199.000	LB	REINFORCING BARS GRADE 60	
1020	540160	378,219.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
1030	541000	39,920.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
1040	562000	569.000	L.F.	BRIDGE JOINT STRIP SEAL	
1050	564000	694.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
1060	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
1070	602000	24.000	C.Y.	RIPRAP CLASS A	
1080	602060	203.000	S.Y.	RIPRAP CLASS G	

(108 Items)

Proposal A300815

Roadway Rehabilitation

Proposal information table

Date Generated: 01/21/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 006 Highway Number:
Items: 45 Counties: Bernalillo

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203000	1,100.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	203211	250.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0030	207000	5,560.000	S.Y.	SUBGRADE PREPARATION	
0040	303000	1,440.000	TON	BASE COURSE	
0050	403701	1,200.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0060	407000	14.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0070	414000	105,000.000	SYIN	COLD MILLING (ASPHALT)	
0080	416000	39,200.000	S.Y.	MINOR PAVEMENT	
0090	417000	1,200.000	S.Y.	MISCELLANEOUS PAVING	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0110	601110	4,370.000	S.Y.	REMOVAL OF SURFACING	
0120	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0130	608004	710.000	S.Y.	CONCRETE SIDEWALK 4"	
0140	609200	530.000	L.F.	HEADER CURB	
0150	609462	2,740.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE C 8" X 32"	
0160	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0170	621000	1.000	LS	MOBILIZATION	
0180	663850	8.000	EACH	WATER VALVE ADJUSTMENT	
0190	701000	60.000	S.F.	PANEL SIGNS	
0200	701100	110.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0210	702610	6.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0220	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0230	704000	20,350.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0240	704002	750.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0250	704700	25,900.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0260	704701	13,000.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0270	704717	15.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0280	704718	12.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0290	704719	29.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING THRU ARROW	

0300	704720	13.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0310	704732	29.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING BIKE SYMBOL (BIKEWAY)	
0320	704735	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
0330	707004	23.000	EACH	TYPE I STANDARD, 4'	
0340	709020	440.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0350	710000	15.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0360	711102	440.000	L.F.	SINGLE CONDUCTOR 2	
0370	713010	12.000	EACH	LOOP VEHICLE DETECTOR	
0380	713020	23.000	EACH	PUSH BUTTON STATION	
0390	713030	5,430.000	L.F.	LOOP DETECTOR WIRE	
0400	713250	120.000	L.F.	LOOP LEAD-IN CABLE	
0410	713300	2,040.000	L.F.	DETECTOR SAW CUT	
0420	721000	3,230.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0430	721101	10.000	EACH	REMOVAL OF PAVEMENT MARKING	
0440	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0450	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000

(45 Items)