

# Proposal 2101370

## Roadway Reconstruction

### Proposal information table

Date Generated: 02/19/2015 Sections: 1  
Date Revised: Amendments: 0  
Call Order: 001 Highway Number:  
Items: 48 Counties: Eddy

### Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	13,137.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203010	1,369.000	C.Y.	EXCAVATION OF CONTAMINATED SOIL	
0040	203011	1.000	LS	ENVIRONMENTAL CONSTRUCTION MONITORING	
0050	203100	29,695.000	C.Y.	BORROW	
0060	203200	4,742.000	C.Y.	SUBEXCAVATION	
0070	207000	271,200.000	S.Y.	SUBGRADE PREPARATION	
0080	303000	69,810.000	TON	BASE COURSE	
0090	404010	4,900.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0100	407000	141.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0110	408100	621.000	TON	PRIME COAT MATERIAL	
0120	414000	180,500.000	SYIN	COLD MILLING (ASPHALT)	
0130	424003	52,000.000	TON	WMA SP-III COMPLETE	
0140	511030	2,890.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0150	540060	335,020.000	LB	REINFORCING BARS GRADE 60	
0160	570024	230.000	L.F.	24" CULVERT PIPE	
0170	570025	22.000	EACH	24" CULVERT PIPE END SECTION	
0180	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0190	601110	105,000.000	S.Y.	REMOVAL OF SURFACING	
0200	602000	1,090.000	C.Y.	RIPRAP CLASS A	
0210	602010	260.000	C.Y.	RIPRAP CLASS B	
0220	602020	230.000	C.Y.	RIPRAP CLASS C	
0230	603261	13,830.000	L.F.	MULCH SOCKS	
0240	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0250	606001	13,950.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0260	606051	80.000	EACH	END TREATMENT TL-3 END TERMINAL	
0270	606061	2,050.000	L.F.	DRAINAGE STRUCTURE PROTECTION SYSTEM	
0280	606610	1,000.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0290	606619	14,000.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0300	607004	119,000.000	L.F.	BARBED WIRE FENCE 4'	

0310	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT
0320	621000	1.000	LS	MOBILIZATION
0330	631000	112,295.000	L.F.	RUMBLE STRIPS
0340	632000	71.000		ACRE CLASS A SEEDING
0350	701031	74.000		EACH REMOVE AND RESET TRAFFIC SIGN
0360	701100	10,710.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS
0370	702000	830.000	S.F.	CONSTRUCTION SIGNING
0380	702100	620.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING
0390	702110	34.000		EACH PORTABLE SIGN SUPPORT
0400	702238	8.000		EACH BARRICADE, TYPE III-8'
0410	702320	110.000		EACH VERTICAL PANEL, TYPE BACK TO BACK
0420	702525	24.000		EACH CHANNELIZATION DEVICES TYPE DRUM
0430	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN
0440	702710	4.000		EACH MOBILE TRAFFIC SIGNAL SYSTEM
0450	704099	180,660.000	L.F.	TEMPORARY STRIPING
0460	704700	156,500.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"
0470	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR
0480	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL

**(48 Items)**

# Proposal 5100810

## Bridge Replacement

### Proposal information table

Date Generated: 02/19/2015 Sections: 2  
Date Revised: Amendments: 0  
Call Order: 002 Highway Number:  
Items: 49 Counties: Torrance

### Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203100	2,000.000	C.Y.	BORROW	
0030	203200	1,000.000	C.Y.	SUBEXCAVATION	
0040	207000	3,500.000	S.Y.	SUBGRADE PREPARATION	
0050	303000	890.000	TON	BASE COURSE	
0060	403701	45.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0070	416000	2,600.000	S.Y.	MINOR PAVEMENT	
0080	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0090	570024	28.000	L.F.	24" CULVERT PIPE	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0110	603262	600.000	L.F.	COMPOSTED MULCH SOCKS	
0120	606001	1,050.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0130	606051	2.000		EACH END TREATMENT TL-3 END TERMINAL	
0140	606053	2.000		EACH END TREATMENT W-BEAM END ANCHOR	
0150	606062	4.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0160	606542	280.000	L.F.	CONCRETE WALL BARRIER 42"	
0170	606619	1,960.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0180	606620	1,960.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0190	607004	600.000	L.F.	BARBED WIRE FENCE 4'	
0200	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0210	621000	1.000	LS	MOBILIZATION	
0220	623012	2.000		EACH MEDIAN DROP INLET TYPE I (RURAL) H=3'1" TO 6'0"	
0230	623095	1.000		EACH MEDIAN DROP INLET 10'X5' (RURAL) H=6'1" TO 9'0"	
0240	631000	1,000.000	L.F.	RUMBLE STRIPS	
0250	632000	1.000		ACRE CLASS A SEEDING	
0260	632020	1.000		ACRE CLASS C SEEDING	
0270	701000	200.000	S.F.	PANEL SIGNS	
0280	701020	75.000	S.F.	RETROREFLECTIVE SHEETING FIELD OVERLAY PANELS	
0290	701030	4.000		EACH REMOVE AND RESET PANEL SIGN	
0300	701100	403.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0310	702000	1,450.000	S.F.	CONSTRUCTION SIGNING	

0320 702100 2,282.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING
0330 702525 108.000		EACH CHANNELIZATION DEVICES TYPE DRUM
0340 702600 2.000		EACH SEQUENTIAL ARROW DISPLAY
0350 702610 2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN
0360 703400 24.000		EACH 1/10TH MILE DELINEATOR
0370 704002 17,550.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"
0380 704099 1,600.000	L.F.	TEMPORARY STRIPING
0390 720060 2.000		EACH VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES
0400 720110 2.000		EACH REMOVE/RESET IMPACT ATTENUATOR UNIT
0410 721000 2,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE
0420 801000 1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR
<b>Section 0002: MAJOR STRUCTURES</b>		
0430 210000 2,200.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES
0440 511030 2,884.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA
0450 516000 35.000	C.Y.	FLOWABLE FILL
0460 540060 739,660.000	LB	REINFORCING BARS GRADE 60
0470 601000 1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS
0480 602000 110.000	C.Y.	RIPRAP CLASS A
0490 602060 90.000	S.Y.	RIPRAP CLASS G

**(49 Items)**

# Proposal 6101100

Bridge New Construction

## Proposal information table

Date Generated: 02/19/2015 Sections: 2  
Date Revised: Amendments: 0  
Call Order: 003 Highway Number:  
Items: 45 Counties: Cibola

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	2,400.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	10,400.000	C.Y.	BORROW	
0040	203301	1,000.000	C.Y.	ROCK EXCAVATION	
0050	207000	2,500.000	S.Y.	SUBGRADE PREPARATION	
0060	303000	1,300.000	TON	BASE COURSE	
0070	403701	60.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0080	405000	7,700.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0090	407000	3.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0100	408100	6.000	TON	PRIME COAT MATERIAL	
0110	414000	5,200.000	SYIN	COLD MILLING (ASPHALT)	
0120	416000	3,400.000	S.Y.	MINOR PAVEMENT	
0130	570012	1,400.000	L.F.	12" CULVERT PIPE	
0140	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0150	601110	2,000.000	S.Y.	REMOVAL OF SURFACING	
0160	602000	40.000	C.Y.	RIPRAP CLASS A	
0170	603051	1.000	LS	CLEAN WATER ACT COMPLIANCE WORK PLAN	\$10,000.00000
0180	603100	6.000	ACRE	TEMPORARY SOIL STABILANT	
0190	603262	1,638.000	L.F.	COMPOSTED MULCH SOCKS	
0200	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0210	604002	2,500.000	S.Y.	GEOTEXTILE CLASS 2	
0220	606001	2,400.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0230	606051	3.000	EACH	END TREATMENT TL-3 END TERMINAL	
0240	606062	5.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0250	606542	510.000	L.F.	CONCRETE WALL BARRIER 42"	
0260	606619	4,000.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0270	606620	3,300.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0280	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0290	621000	1.000	LS	MOBILIZATION	
0300	631000	2,150.000	L.F.	RUMBLE STRIPS	
0310	632000	5.000	ACRE	CLASS A SEEDING	

0320	632020	0.300	ACRE CLASS C SEEDING	
0330	702610	2.000	EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0340	702810	1.000	LS TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0350	703400	2.000	EACH 1/10TH MILE DELINEATOR	
0360	704701	17,100.000	L.F. HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0370	720100	1.000	EACH SAND BARREL VEHICULAR IMPACT ATTENUATOR UNIT	
0380	720110	3.000	EACH REMOVE/RESET IMPACT ATTENUATOR UNIT	
0390	801000	1.000	LS CONSTRUCTION STAKING BY THE CONTRACTOR	
0400	802000	1.000	LS POST CONSTRUCTION PLANS	\$10,000.00000
0410	901000	1.000	LS CONTRACTOR PROCESS QUALITY CONTROL	

**Section 0002: MAJOR STRUCTURES**

0420	210000	2,200.000	C.Y. EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES
0430	511030	680.000	C.Y. STRUCTURAL CONCRETE, CLASS AA
0440	540060	154,000.000	LB REINFORCING BARS GRADE 60
0450	602000	30.000	C.Y. RIPRAP CLASS A

**(45 Items)**

# Proposal 4101170

Bridge Rehabilitation

## Proposal information table

Date Generated: 02/19/2015 Sections: 2  
Date Revised: Amendments: 0  
Call Order: 004 Highway Number:  
Items: 15 Counties: Guadalupe

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: BRIDGE</b>					
0010	512003	18.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0020	530300	2,500.000	LB	REPLACEMENT REINFORCING BARS GRADE 60	
0030	533000	850.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0040	536001	3,632.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0050	540160	3,710.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0060	546000	1.000	LS	RECOATING STRUCTURES	
0070	546200	4,372.000	S.F.	SP 3 POWER TOOL CLEANING AND PRIMING	
0080	546210	3,196.000	S.F.	SP 11 POWER TOOL CLEANING AND PRIMING	
0090	562000	208.000	L.F.	BRIDGE JOINT STRIP SEAL	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0110	621000	1.000	LS	MOBILIZATION	
<b>Section 0002: CONSTRUCTION ENGINEERING</b>					
0120	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0130	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0140	702610	4.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0150	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	

(15 Items)

# Proposal 6100825

## Bridge Rehabilitation

### Proposal information table

Date Generated: 02/19/2015 Sections: 2  
Date Revised: Amendments: 0  
Call Order: 005 Highway Number:  
Items: 18 Counties: Cibola

### Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: BRIDGE</b>					
0010	512000	4.000	C.Y.	SUPERSTRUCTURE CONCRETE	
0020	529000	1.000	LS	PIER AND ABUTMENT BEARING MODIFICATIONS	
0030	532000	100.000	S.Y.	PENETRATING WATER REPELLENT TREATMENT	
0040	533000	100.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0050	535100	3,656.000	S.Y.	CONCRETE SURFACE TREATMENT	
0060	536001	3,656.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0070	540160	480.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0080	561000	70.000	L.F.	ELASTOMERIC COMPRESSION JOINT SEAL REPLACEMENT	
0090	562000	74.000	L.F.	BRIDGE JOINT STRIP SEAL	
0100	562001	177.000	L.F.	BRIDGE JOINT ELASTOMER	
0110	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0120	621000	1.000	LS	MOBILIZATION	
<b>Section 0002: CONSTRUCTION SIGNING</b>					
0130	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0140	618011	1.000	LS	PUBLIC AWARENESS	\$1,500.00000
0150	690001	1.000	ALOW	RAILWAY FLAGGING	\$10,000.00000
0160	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0170	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0180	704700	3,325.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	

(18 Items)

# Proposal 6100299

Stockpiling

## Proposal information table

Date Generated:	02/19/2015	Sections:	1
Date Revised:		Amendments:	0
Call Order:	006	Highway Number:	
Items:	5	Counties:	McKinley Cibola

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	410311	18,838.000	C.Y.	STOCKPILED SURFACE TREATMENT AGGREGATE 1/2"	
0020	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0030	621000	1.000	LS	MOBILIZATION	
0040	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0050	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	

**(5 Items)**