

Proposal 2100140

Roadway Reconstruction

Proposal information table

Date Generated: 03/19/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 93 Counties: Curry

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	34,700.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	300.000	C.Y.	BORROW	
0040	203200	2,500.000	C.Y.	SUBEXCAVATION	
0050	206000	500.000	C.Y.	UNSUITABLE MATERIAL EXCAVATION	
0060	303000	18,410.000	TON	BASE COURSE	
0070	306102	55,070.000	S.Y.	LIME TREATED SUBGRADE 12"	
0080	402460	1,450.000	TON	HYDRATED LIME	
0090	416000	2,480.000	S.Y.	MINOR PAVEMENT	
0100	450060	80.000	S.Y.	CONCRETE PAVEMENT-6"	
0110	450100	43,400.000	S.Y.	CONCRETE PAVEMENT-10"	
0120	452000	34,500.000	L.F.	SEALING CONCRETE PAVEMENT JOINTS	
0130	502030	306.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0140	511000	1.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0150	515000	3.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0160	516000	439.000	C.Y.	FLOWABLE FILL	
0170	540060	7,661.000	LB	REINFORCING BARS GRADE 60	
0180	570419	41.000	L.F.	15" STORM DRAIN CULVERT PIPE	
0190	570425	554.000	L.F.	18" STORM DRAIN CULVERT PIPE	
0200	570437	2,034.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0210	570441	1.000	EACH	24" STORM DRAIN CULVERT PIPE END SECTION	
0220	570461	231.000	L.F.	36" STORM DRAIN CULVERT PIPE	
0230	570473	2,193.000	L.F.	48" STORM DRAIN CULVERT PIPE	
0240	570493	1,333.000	L.F.	66" STORM DRAIN CULVERT PIPE	
0250	570498	1.000	EACH	66" STORM DRAIN CULVERT PIPE END SECTION	
0260	570620	133.000	L.F.	28"SX18"R STORM DRAIN CPA	
0270	570623	1.000	EACH	28"SX18"R STORM DRAIN CPA END SECTION	
0280	570630	415.000	L.F.	43"SX26"R STORM DRAIN CPA	
0290	570633	1.000	EACH	43"SX26"R STORM DRAIN CPA END SECTION	
0300	570650	430.000	L.F.	73"SX45"R STORM DRAIN CPA	
0310	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	

0320	601110	48,040.000	S.Y.	REMOVAL OF SURFACING	
0330	602000	65.000	C.Y.	RIPRAP CLASS A	
0340	603100	2.000	ACRE	TEMPORARY SOIL STABILANT	
0350	603150	6,340.000	S.Y.	SOIL RETENTION BLANKET	
0360	603261	2,022.000	L.F.	MULCH SOCKS	
0370	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0380	606610	420.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0390	606619	720.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0400	608004	3,120.000	S.Y.	CONCRETE SIDEWALK 4"	
0410	608106	1,580.000	S.Y.	DRIVE PAD 6"	
0420	608404	370.000	S.Y.	CONCRETE MEDIAN PAVEMENT 4" (COLORED AND PATTERNED)	
0430	609200	710.000	L.F.	HEADER CURB	
0440	609430	11,180.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 30"	
0450	609478	4,190.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	
0460	609636	930.000	L.F.	CONCRETE VALLEY GUTTER 6" X 36"	
0470	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0480	617000	1.000	LS	VIBRATION MONITORING	
0490	617003	1.000	LS	VIDEO TAPING	
0500	617004	1.000	LS	VIBRATION RISK SURVEY	
0510	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0520	618011	1.000	LS	PUBLIC AWARENESS	\$7,500.00000
0530	621000	1.000	LS	MOBILIZATION	
0540	623001	16.000		EACH MEDIAN DROP INLET TYPE I (URBAN) H=3'1" TO 6'0"	
0550	623311	7.000		EACH CURB DROP INLET TYPE I-B, 0' TO 4'	
0560	623312	4.000		EACH CURB DROP INLET TYPE II-B, 0' TO 4'	
0570	623313	3.000		EACH CURB DROP INLET TYPE III-B, 0' TO 4'	
0580	623331	4.000		EACH CURB DROP INLET TYPE I-B, OVER 4'	
0590	623332	19.000		EACH CURB DROP INLET TYPE II-B, OVER 4'	
0600	623333	7.000		EACH CURB DROP INLET TYPE III-B, OVER 4'	
0610	623401	3.000		EACH DROP INLET 4'X4'(TYPE I) H=4'-0"	
0620	623404	2.000		EACH DROP INLET 4'X4' (TYPE I) H=4'-1" TO 6'-0"	
0630	632020	6.000		ACRE CLASS C SEEDING	
0640	662000	1.000		EACH MANHOLE TYPE C-4' DIAMETER 0' TO 6' DEPTH	
0650	662010	6.000		EACH MANHOLE TYPE C-6' DIAMETER 0' TO 6' DEPTH	
0660	662040	3.000		EACH MANHOLE TYPE C-8' DIAMETER 0' TO 6' DEPTH	
0670	662042	6.000		EACH MANHOLE TYPE C-8' DIAMETER OVER 6' TO 10' DEPTH	
0680	662100	8.000		EACH SPECIAL MANHOLE	
0690	662400	2.000		EACH MANHOLE ADJUSTMENT	
0700	663049	1.000	LS	PRECONSTRUCTION UTILITY SURVEY	
0710	667110	14.000		EACH MAIL BOX INSTALLATION-SINGLE	

0720	701000	480.000	S.F.	PANEL SIGNS	
0730	701100	820.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0740	702000	1,784.000	S.F.	CONSTRUCTION SIGNING	
0750	702100	1,281.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0760	702110	55.000		EACH PORTABLE SIGN SUPPORT	
0770	702238	30.000		EACH BARRICADE, TYPE III-8'	
0780	702320	87.000		EACH VERTICAL PANEL, TYPE BACK TO BACK	
0790	702525	165.000		EACH CHANNELIZATION DEVICES TYPE DRUM	
0800	702600	2.000		EACH SEQUENTIAL ARROW DISPLAY	
0810	702610	4.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0820	704000	49,680.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0830	704002	13,885.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0840	704100	6,745.000	L.F.	REMOVABLE MARKING TAPE	
0850	704814	647.000	L.F.	TYPE I RETROREFLECTIVE PREFORMED PAVEMENT STRIPE 24"	
0860	704817	4.000	EACH	TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING RIGHT ARROW	
0870	704818	40.000	EACH	TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING LEFT ARROW	
0880	704820	6.000	EACH	TYPE I RETROREFLECTIVE PREFORMED PAVEMENT MARKING WORD (ONLY)	
0890	709020	9,088.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0900	710000	9.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0910	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0920	802000	1.000	LS	POST CONSTRUCTION PLANS	\$10,000.00000
0930	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(93 Items)

Proposal 6100470

Bridge Replacement

Proposal information table

Date Generated: 03/19/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 48 Counties: McKinley

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203000	100.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	203211	200.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0030	207000	800.000	S.Y.	SUBGRADE PREPARATION	
0040	303015	760.000	S.Y.	BASE COURSE	
0050	416000	760.000	S.Y.	MINOR PAVEMENT	
0060	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0070	570024	6.000	L.F.	24" CULVERT PIPE	
0080	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0090	601110	1,170.000	S.Y.	REMOVAL OF SURFACING	
0100	601300	1.000	LS	DEMOLITION	
0110	601998	50.000	L.F.	REMOVAL AND DISPOSAL OF AC CONDUIT PIPE (SINGLE CONDUIT)	
0120	603051	1.000	LS	CLEAN WATER ACT COMPLIANCE WORK PLAN	
0130	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0140	606620	270.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0150	607066	150.000	L.F.	VINYL COATED CHAIN LINK FENCE 6'	
0160	608004	250.000	S.Y.	CONCRETE SIDEWALK 4"	
0170	608106	50.000	S.Y.	DRIVE PAD 6"	
0180	609200	30.000	L.F.	HEADER CURB	
0190	609424	440.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	
0200	617000	1.000	LS	VIBRATION MONITORING	
0210	617003	1.000	LS	VIDEO TAPING	
0220	617004	1.000	LS	VIBRATION RISK SURVEY	
0230	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0240	618011	1.000	LS	PUBLIC AWARENESS	
0250	621000	1.000	LS	MOBILIZATION	
0260	623313	2.000		EACH CURB DROP INLET TYPE III-B, 0' TO 4'	
0270	662400	4.000		EACH MANHOLE ADJUSTMENT	
0280	663855	3.000		EACH ADJUST VALVE BOX TO GRADE	
0290	663865	1.000		EACH ADJUST WATER METER TO GRADE	

0300 664000 1.000	LS	LANDSCAPE, COMPLETE	
0310 701000 25.000	S.F.	PANEL SIGNS	
0320 701100 60.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0330 702610 3.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0340 702810 1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0350 704000 800.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0360 720060 1.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0370 801000 1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0380 802000 1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000

Section 0002: MAJOR STRUCTURE

0390 203100 3,500.000	C.Y.	BORROW	
0400 203301 110.000	C.Y.	ROCK EXCAVATION	
0410 210000 800.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0420 511030 450.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0430 516000 140.000	C.Y.	FLOWABLE FILL	
0440 518298 616.000	S.F.	PRECAST DECK PANELS 6 IN. DEPTH	
0450 540060 155,500.000	LB	REINFORCING BARS GRADE 60	
0460 541000 5,100.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
0470 564000 143.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
0480 601000 1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	

(48 Items)

Proposal 4101180

Bridge Rehabilitation

Proposal information table

Date Generated: 03/19/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 14 Counties: Mora Colfax

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	455000	1,658.000	S.Y.	DIAMOND GRINDING OF PCCP	
0020	533000	562.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0030	536001	2,091.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0040	540160	100.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0050	546000	1.000	LS	RECOATING STRUCTURES	
0060	546200	422.000	S.F.	SP 3 POWER TOOL CLEANING AND PRIMING	
0070	546210	2,160.000	S.F.	SP 11 POWER TOOL CLEANING AND PRIMING	
0080	564000	183.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
0090	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0100	621000	1.000	LS	MOBILIZATION	
Section 0002: CONSTRUCTION ENGINEERING					
0110	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0120	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0130	702610	4.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0140	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	

(14 Items)