

Proposal F100110

Roadway Reconstruction

Proposal information table

Date Generated: 04/15/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 109 Counties: San Juan
Project ID: F100110

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	38,000.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	10,000.000	C.Y.	BORROW	
0040	203200	10,000.000	C.Y.	SUBEXCAVATION	
0050	203211	1,000.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0060	207000	149,900.000	S.Y.	SUBGRADE PREPARATION	
0070	210000	1,900.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0080	303000	48,030.000	TON	BASE COURSE	
0090	403701	4,620.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0100	405000	3,750.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0110	407000	46.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0120	408100	274.000	TON	PRIME COAT MATERIAL	
0130	416000	16,090.000	S.Y.	MINOR PAVEMENT	
0140	423282	49,680.000	TON	HMA SP-III COMPLETE	
0150	511030	140.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0160	515000	90.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0170	533000	20.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0180	540060	24,000.000	LB	REINFORCING BARS GRADE 60	
0190	541200	5,500.000	LB	STRUCTURAL STEEL FOR MISCELLANEOUS STRUCTURES	
0200	570018	52.000	L.F.	18" CULVERT PIPE	
0210	570024	2,045.000	L.F.	24" CULVERT PIPE	
0220	570025	5.000	EACH	24" CULVERT PIPE END SECTION	
0230	570437	2,500.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0240	570461	202.000	L.F.	36" STORM DRAIN CULVERT PIPE	
0250	570465	1.000	EACH	36" STORM DRAIN CULVERT PIPE END SECTION	
0260	570467	134.000	L.F.	42" STORM DRAIN CULVERT PIPE	
0270	570471	2.000	EACH	42" STORM DRAIN CULVERT PIPE END SECTION	
0280	571144	166.000	L.F.	144" STRUCTURAL PLATE PIPE	

0290	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0300	601110	102,300.000	S.Y.	REMOVAL OF SURFACING	
0310	602000	300.000	C.Y.	RIPRAP CLASS A	
0320	602060	120.000	S.Y.	RIPRAP CLASS G	
0330	603100	12.000	ACRE	TEMPORARY SOIL STABILANT	
0340	603221	180.000	L.F.	CHECK DAM TYPE II	
0350	603250	16.000	EACH	DROP INLET PROTECTION TYPE I	
0360	603260	60.000	S.Y.	CULVERT PROTECTION	
0370	603262	5,400.000	L.F.	COMPOSTED MULCH SOCKS	
0380	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0390	604002	149,870.000	S.Y.	GEOTEXTILE CLASS 2	
0400	604310	149,870.000	S.Y.	GEOGRID BASE REINFORCEMENT	
0410	606001	2,175.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0420	606011	250.000	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0430	606051	4.000	EACH	END TREATMENT TL-3 END TERMINAL	
0440	606053	5.000	EACH	END TREATMENT W-BEAM END ANCHOR	
0450	606054	1.000	EACH	END TREATMENT THRIE-BEAM END ANCHOR	
0460	606055	5.000	EACH	END TREATMENT DRIVEWAY END ANCHOR	
0470	606542	677.000	L.F.	CONCRETE WALL BARRIER 42"	
0480	606619	10,600.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0490	606620	10,700.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0500	607004	2,200.000	L.F.	BARBED WIRE FENCE 4'	
0510	607026	400.000	L.F.	CHAIN LINK FENCE 6'	
0520	607210	190.000	L.F.	REMOVE AND REBUILD WOVEN WIRE FENCE	
0530	607312	3.000	EACH	STANDARD GATE, 12'	
0540	607314	9.000	EACH	STANDARD GATE, 14'	
0550	607408	14.000	EACH	CHAIN LINK GATE, 8' (SPAN)	
0560	607414	4.000	EACH	CHAIN LINK GATE, 14' (SPAN)	
0570	607512	2.000	EACH	PIPE GATE 12'	
0580	608304	6,520.000	S.Y.	CONCRETE MEDIAN PAVEMENT 4" (COLORED)	
0590	609109	2,420.000	L.F.	PINNED CURB	
0600	609324	19,980.000	L.F.	CONCRETE SLOPED CURB AND GUTTER 6" X 24"	
0610	609424	570.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	
0620	609650	100.000	L.F.	CONCRETE VALLEY GUTTER 6" X 72"	
0630	610014	2.000	EACH	CATTLE GUARD 14'	
0640	617003	1.000	LS	VIDEO TAPING	
0650	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0660	618011	1.000	LS	PUBLIC AWARENESS	\$20,000.00000
0670	621000	1.000	LS	MOBILIZATION	
0680	623027	1.000	EACH	MEDIAN DROP INLET TYPE II (RURAL)	
0690	623301	3.000	EACH	CURB DROP INLET TYPE I-A, 0' TO 4'	
0700	623321	1.000	EACH	CURB DROP INLET TYPE I-A, OVER 4'	

0710	623401	7.000	EACH	DROP INLET 4'X4'(TYPE I) H=4'-0"	
0720	623402	10.000	EACH	DROP INLET 4'X4' (TYPE II) H=4'-0"	
0730	632000	8.000	ACRE	CLASS A SEEDING	
0740	632020	2.000	ACRE	CLASS C SEEDING	
0750	662010	10.000	EACH	MANHOLE TYPE C-6' DIAMETER 0' TO 6' DEPTH	
0760	662072	1.000	EACH	MANHOLE TYPE E-6' DIAMETER OVER 6' TO 10' DEPTH	
0770	664052	40.000	EACH	POPPULUS FREMONTII 'WISLIZENII'(RIO GRANDE VALLEY COTTONWOOD	
0780	667110	9.000	EACH	MAIL BOX INSTALLATION-SINGLE	
0790	667120	1.000	EACH	MAIL BOX INSTALLATION-DOUBLE	
0800	667130	50.000	EACH	MAIL BOX INSTALLATION-MULTIPLE	
0810	701000	1,300.000	S.F.	PANEL SIGNS	
0820	701030	7.000	EACH	REMOVE AND RESET PANEL SIGN	
0830	701100	2,950.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0840	702000	4,250.000	S.F.	CONSTRUCTION SIGNING	
0850	702100	4,050.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0860	702238	120.000	EACH	BARRICADE, TYPE III-8'	
0870	702525	450.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0880	702600	3.000	EACH	SEQUENTIAL ARROW DISPLAY	
0890	702610	4.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0900	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$30,000.00000
0910	703001	20.000	EACH	OBJECT MARKER TYPE 1	
0920	704000	131,300.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0930	704099	198,500.000	L.F.	TEMPORARY STRIPING	
0940	704701	4,750.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0950	704717	38.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0960	704718	53.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0970	704720	51.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0980	720050	1.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
0990	720060	5.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
1000	720110	5.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
1010	721000	70,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
1020	721101	3.000	EACH	REMOVAL OF PAVEMENT MARKING	
1030	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
1040	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
1050	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

Section 0002: MAJOR STRUCTURES

1060 210000 470.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES
1070 511030 190.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA
1080 533000 20.000	S.Y.	REPAIR OF CONCRETE STRUCTURES
1090 540060 31,800.000	LB	REINFORCING BARS GRADE 60

(109 Items)

Proposal 6100650

Roadway Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 27 Counties: McKinley
Project ID: 6100650

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	403701	6,580.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0020	407000	66.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	414000	1,258,580.000	SYIN	COLD MILLING (ASPHALT)	
0040	423282	61,180.000	TON	HMA SP-III COMPLETE	
0050	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0060	606001	9,050.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0070	606051	18.000		EACH END TREATMENT TL-3 END TERMINAL	
0080	606053	14.000		EACH END TREATMENT W-BEAM END ANCHOR	
0090	606062	4.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0100	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0110	621000	1.000	LS	MOBILIZATION	
0120	622002	1.000		EACH FIELD LABORATORY, TYPE II	
0130	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	
0140	631000	126,780.000	L.F.	RUMBLE STRIPS	
0150	701000	490.000	S.F.	PANEL SIGNS	
0160	701100	770.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0170	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0180	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0190	703100	24.000		EACH ROAD DELINEATOR TYPE GUIDE	
0200	703110	6.000		EACH ROAD DELINEATOR TYPE HAZARD	
0210	704700	9,600.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0220	704701	142,800.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0230	704856	72.000		EACH REFLECTIVE RAISED PAVEMENT MARKER TYPE C	
0240	704860	12.000		EACH REFLECTIVE RAISED PAVEMENT MARKER TYPE J	
0250	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0260	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
0270	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(27 Items)

Proposal 1100611

Bridge Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 87 Counties: Hidalgo
Project ID: 1100611

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	10,043.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	3,844.000	C.Y.	BORROW	
0040	207000	14,431.000	S.Y.	SUBGRADE PREPARATION	
0050	302000	13,500.000	S.Y.	PROCESSING, PLACING AND COMPACTING EXISTING PAVEMENT	
0060	303000	3,973.000	TON	BASE COURSE	
0070	404010	364.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0080	405000	11,778.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0090	407000	19.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0100	408100	46.000	TON	PRIME COAT MATERIAL	
0110	414000	206,074.000	SYIN	COLD MILLING (ASPHALT)	
0120	423282	11,006.000	TON	HMA SP-III COMPLETE	
0130	511000	100.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0140	511030	60.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0150	516000	15.000	C.Y.	FLOWABLE FILL	
0160	540060	9,800.000	LB	REINFORCING BARS GRADE 60	
0170	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0180	570024	150.000	L.F.	24" CULVERT PIPE	
0190	570025	6.000	EACH	24" CULVERT PIPE END SECTION	
0200	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0210	602000	140.000	C.Y.	RIPRAP CLASS A	
0220	602030	140.000	C.Y.	RIPRAP CLASS D	
0230	602200	30.000	C.Y.	GABIONS	
0240	603100	6.500	ACRE	TEMPORARY SOIL STABILANT	
0250	603221	75.000	L.F.	CHECK DAM TYPE II	
0260	603252	1.000	EACH	DROP INLET PROTECTION	
0270	603262	1,500.000	L.F.	COMPOSTED MULCH SOCKS	
0280	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	

0290	606001	2,327.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL
0300	606051	4.000		EACH END TREATMENT TL-3 END TERMINAL
0310	606053	2.000		EACH END TREATMENT W-BEAM END ANCHOR
0320	606062	6.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER
0330	606610	7,300.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR
0340	606619	7,300.000	L.F.	RESETTING OF CONCRETE WALL BARRIER
0350	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT
0360	621000	1.000	LS	MOBILIZATION
0370	622002	1.000		EACH FIELD LABORATORY, TYPE II
0380	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY
0390	623114	1.000		EACH MEDIAN DROP INLET 5'X5' (RURAL) H=3'1" TO 6'0"
0400	631000	9,208.000	L.F.	RUMBLE STRIPS
0410	632000	5.500		ACRE CLASS A SEEDING
0420	632020	1.000		ACRE CLASS C SEEDING
0430	701000	575.000	S.F.	PANEL SIGNS
0440	701100	935.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS
0450	702000	737.000	S.F.	CONSTRUCTION SIGNING
0460	702100	1,126.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING
0470	702110	14.000		EACH PORTABLE SIGN SUPPORT
0480	702238	8.000		EACH BARRICADE, TYPE III-8'
0490	702525	75.000		EACH CHANNELIZATION DEVICES TYPE DRUM
0500	702600	2.000		EACH SEQUENTIAL ARROW DISPLAY
0510	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN
0520	703003	8.000		EACH OBJECT MARKER TYPE 3
0530	703100	20.000		EACH ROAD DELINEATOR TYPE GUIDE
0540	704000	22,248.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"
0550	704099	32,412.000	L.F.	TEMPORARY STRIPING
0560	704560	4.000	EACH	RETROREFLECTORIZED PLASTIC WRONG WAY ARROW
0570	704701	39,063.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"
0580	704869	56.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG
0590	704871	10.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PJ
0600	704872	70.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PC
0610	704876	240.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG
0620	704877	240.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TH
0630	720100	1.000		EACH SAND BARREL VEHICULAR IMPACT ATTENUATOR

UNIT

0640	720110	1.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0650	721000	10,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0660	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0670	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
0680	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

Section 0002: BRIDGE

0690	210000	174.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0700	511500	12,401.000	S.F.	SPECIAL SURFACE FINISH	
0710	511601	1.000	LS	WIND BREAK	
0720	511602	1.000	LS	FOGGING SYSTEM	
0730	512003	1,000.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0740	515000	24.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0750	516000	766.000	C.Y.	FLOWABLE FILL	
0760	529000	1.000	LS	PIER AND ABUTMENT BEARING MODIFICATIONS	
0770	530300	200.000	LB	REPLACEMENT REINFORCING BARS GRADE 60	
0780	532000	573.000	S.Y.	PENETRATING WATER REPELLENT TREATMENT	
0790	533000	10.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0800	534000	10.000	GAL	EPOXY INJECTION, TYPE I	
0810	540160	115,234.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0820	541000	6,406.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
0830	543002	610.000	L.F.	METAL RAILING, TYPE A42	
0840	562000	188.000	L.F.	BRIDGE JOINT STRIP SEAL	
0850	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0860	602000	1,006.000	C.Y.	RIPRAP CLASS A	
0870	602060	73.000	S.Y.	RIPRAP CLASS G	

(87 Items)

Proposal 1101020

Roadway Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 004 Highway Number:
Items: 33 Counties: Dona Ana
Project ID: 1101020

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	207000	300.000	S.Y.	SUBGRADE PREPARATION	
0020	303000	90.000	TON	BASE COURSE	
0030	404010	3,500.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0040	405000	280.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0050	407000	68.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0060	411000	30.000	LB	HOT POURED CRACK SEALING	
0070	414000	369,400.000	SYIN	COLD MILLING (ASPHALT)	
0080	424003	17,500.000	TON	WMA SP-III COMPLETE	
0090	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0100	601110	267.000	S.Y.	REMOVAL OF SURFACING	
0110	606001	3,187.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0120	606011	80.000	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0130	606051	8.000		EACH END TREATMENT TL-3 END TERMINAL	
0140	606053	6.000		EACH END TREATMENT W-BEAM END ANCHOR	
0150	606062	3.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0160	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0170	621000	1.000	LS	MOBILIZATION	
0180	702000	710.000	S.F.	CONSTRUCTION SIGNING	
0190	702100	530.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0200	702110	50.000		EACH PORTABLE SIGN SUPPORT	
0210	702238	6.000		EACH BARRICADE, TYPE III-8'	
0220	702525	850.000		EACH CHANNELIZATION DEVICES TYPE DRUM	
0230	702600	2.000		EACH SEQUENTIAL ARROW DISPLAY	
0240	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0250	704099	116,100.000	L.F.	TEMPORARY STRIPING	
0260	704701	81,300.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0270	704876	3,570.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
0280	704877	1,790.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT	

			MARKER, TYPE TH		
0290	721000	35,700.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0300	730100	1.000	LS	AUTOMATIC TRAFFIC RECORDER AND AUTOMATIC VEHICLE CLASSIFICAT ION SYSTEM	
0310	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0320	802000	1.000	LS	POST CONSTRUCTION PLANS	\$1,500.00000
0330	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(33 Items)

Proposal 3100460

Roadway Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 1
Date Revised: Amendments: 0
Call Order: 005 Highway Number:
Items: 34 Counties: Valencia
Project ID: 3100460

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	403701	2,390.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0020	407000	29.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	407001	30.000	TON	FOG SEAL	
0040	414000	256,800.000	SYIN	COLD MILLING (ASPHALT)	
0050	416000	84,900.000	S.Y.	MINOR PAVEMENT	
0060	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0070	606001	125.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0080	606011	87.500	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0090	606051	2.000		EACH END TREATMENT TL-3 END TERMINAL	
0100	606054	2.000		EACH END TREATMENT THRIE-BEAM END ANCHOR	
0110	608004	135.000	S.Y.	CONCRETE SIDEWALK 4"	
0120	609200	170.000	L.F.	HEADER CURB	
0130	609418	220.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6"X18"	
0140	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0150	621000	1.000	LS	MOBILIZATION	
0160	662400	8.000		EACH MANHOLE ADJUSTMENT	
0170	663850	1.000		EACH WATER VALVE ADJUSTMENT	
0180	702610	4.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0190	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0200	703205	11.000		EACH TUBULAR FLEXIBLE TRAFFIC MARKER	
0210	704000	103,000.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0220	704002	400.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 6"	
0230	704700	94,200.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0240	704701	5,800.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0250	704717	8.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0260	704718	62.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0270	704720	16.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	

0280 707004 10.000	EACH TYPE I STANDARD, 4'	
0290 709020 110.000	L.F. RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0300 710000 1.000	EACH ELECTRICAL PULL BOX (STANDARD)	
0310 711102 110.000	L.F. SINGLE CONDUCTOR 2	
0320 713020 16.000	EACH PUSH BUTTON STATION	
0330 801000 1.000	LS CONSTRUCTION STAKING BY THE CONTRACTOR	
0340 802000 1.000	LS POST CONSTRUCTION PLANS	\$10,000.00000

(34 Items)

Proposal A300696

Bridge Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 006 Highway Number:
Items: 15 Counties: Bernalillo
Project ID: A300696

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	533000	11.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0020	536001	17,308.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0030	621000	1.000	LS	MOBILIZATION	
Section 0002: CONSTRUCTION ENGINEERING					
0040	606610	480.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0050	606619	1,440.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0060	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0070	702610	10.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0080	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0090	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$20,000.00000
0100	704701	10,400.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0110	704717	1.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0120	704718	16.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0130	704720	9.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0140	720060	1.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0150	720110	3.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	

(15 Items)

Proposal 2100870

Bridge Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 007 Highway Number:
Items: 36 Counties: Guadalupe
Project ID: 2100870

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0020	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0030	606001	2,790.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0040	606011	75.000	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0050	606051	4.000	EACH	END TREATMENT TL-3 END TERMINAL	
0060	606610	560.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0070	606619	560.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0080	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0090	618011	1.000	LS	PUBLIC AWARENESS	\$3,500.00000
0100	621000	1.000	LS	MOBILIZATION	
0110	702000	700.000	S.F.	CONSTRUCTION SIGNING	
0120	702100	1,150.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0130	702238	1.000	EACH	BARRICADE, TYPE III-8'	
0140	702525	50.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0150	702610	4.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0160	702710	1.000	EACH	MOBILE TRAFFIC SIGNAL SYSTEM	
0170	704000	25,500.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0180	704100	1,120.000	L.F.	REMOVABLE MARKING TAPE	
0190	720060	2.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0200	721000	1,120.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0210	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0220	802000	1.000	LS	POST CONSTRUCTION PLANS	\$1,500.00000
Section 0002: BRIDGE					
0230	210000	6.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0240	512006	8.000	C.Y.	SPECIAL CONCRETE	
0250	533000	150.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0260	533001	1,000.000	EACH	EMBEDDED GALVANIC ANODES	
0270	536001	845.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE	

DECK OVERLAY

0280	540160	1,630.000	LB	EPOXY COATED REINFORCING BARS GRADE 60
0290	541000	1,150.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES
0300	546000	1.000	LS	RECOATING STRUCTURES
0310	546210	20.000	S.F.	SP 11 POWER TOOL CLEANING AND PRIMING
0320	562000	108.000	L.F.	BRIDGE JOINT STRIP SEAL
0330	570012	200.000	L.F.	12" CULVERT PIPE
0340	570013	2.000	EACH	12" CULVERT PIPE END SECTION
0350	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS
0360	602000	5.000	C.Y.	RIPRAP CLASS A

(36 Items)

Proposal S100311

Bridge-Rehabilitation

Proposal information table

Date Generated: 04/16/2015 Sections: 2
Date Revised: Amendments: 0
Call Order: 008 Highway Number:
Items: 39 Counties: Santa Fe
Project ID: S100311

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	207000	1,180.000	S.Y.	SUBGRADE PREPARATION	
0030	303160	180.000	S.Y.	BASE COURSE 6"	
0040	414000	2,900.000	SYIN	COLD MILLING (ASPHALT)	
0050	416000	2,600.000	S.Y.	MINOR PAVEMENT	
0060	417100	90.000	L.F.	ASPHALT CURB	
0070	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0080	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0090	606001	325.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0100	606051	2.000		EACH END TREATMENT TL-3 END TERMINAL	
0110	606052	4.000		EACH END TREATMENT TL-2 END TERMINAL	
0120	606062	4.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0130	606619	400.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0140	606620	400.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0150	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0160	618011	1.000	LS	PUBLIC AWARENESS	\$5,000.00000
0170	621000	1.000	LS	MOBILIZATION	
0180	701000	95.000	S.F.	PANEL SIGNS	
0190	701010	95.000	S.F.	EXTRUDED PANEL SIGNS	
0200	701100	200.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0210	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0220	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0230	704000	3,700.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0240	720060	2.000		EACH VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0250	720110	2.000		EACH REMOVE/RESET IMPACT ATTENUATOR UNIT	
0260	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0270	802000	1.000	LS	POST CONSTRUCTION PLANS	\$2,000.00000
Section 0002: BRIDGE					
0280	511000	10.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	

0290	511500	3,000.000	S.F.	SPECIAL SURFACE FINISH
0300	529000	1.000	LS	PIER AND ABUTMENT BEARING MODIFICATIONS
0310	530300	500.000	LB	REPLACEMENT REINFORCING BARS GRADE 60
0320	533000	360.000	S.Y.	REPAIR OF CONCRETE STRUCTURES
0330	533001	500.000	EACH	EMBEDDED GALVANIC ANODES
0340	536001	825.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY
0350	540060	3,500.000	LB	REINFORCING BARS GRADE 60
0360	541000	4,700.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES
0370	562000	74.000	L.F.	BRIDGE JOINT STRIP SEAL
0380	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS
0390	601110	720.000	S.Y.	REMOVAL OF SURFACING

(39 Items)