

Proposal ER14103

Roadway Reconstruction

Proposal information table

Date Generated: 04/21/2016 Sections: 2
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 68 Counties: Catron
Project ID: ER14103

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|------------|------|---|---------------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 201000 | 1.000 | LS | CLEARING AND GRUBBING | |
| 0020 | 203000 | 17,900.000 | C.Y. | UNCLASSIFIED EXCAVATION | |
| 0030 | 203100 | 13,800.000 | C.Y. | BORROW | |
| 0040 | 203211 | 300.000 | S.Y. | UNSTABLE SUBGRADE STABILIZATION | |
| 0050 | 203300 | 100.000 | L.F. | CONTROLLED BLASTING | |
| 0060 | 203301 | 7,100.000 | C.Y. | ROCK EXCAVATION | |
| 0070 | 207000 | 12,700.000 | S.Y. | SUBGRADE PREPARATION | |
| 0080 | 208000 | 1.600 | MILE | LINEAR GRADING | |
| 0090 | 303000 | 4,000.000 | TON | BASE COURSE | |
| 0100 | 405000 | 1,740.000 | S.Y. | DETOUR PAVEMENT CONSTRUCTION | |
| 0110 | 407001 | 7.000 | TON | FOG SEAL | |
| 0120 | 408100 | 23.000 | TON | PRIME COAT MATERIAL | |
| 0130 | 410000 | 43,000.000 | S.Y. | ONE COURSE SURFACE TREATMENT | |
| 0140 | 410220 | 33.000 | TON | POLYMER MODIFIED HIGH FLOAT EMULSION-100P | |
| 0150 | 417000 | 600.000 | S.Y. | MISCELLANEOUS PAVING | |
| 0160 | 506008 | 16,400.000 | S.F. | MSE BLOCK WALL | |
| 0170 | 506009 | 4,800.000 | S.F. | GRAVITY BLOCK WALL | |
| 0180 | 511000 | 570.000 | C.Y. | STRUCTURAL CONCRETE, CLASS A | |
| 0190 | 515000 | 7.000 | C.Y. | REINF.CONCRETE FOR MINOR STRUCTURES | |
| 0200 | 540060 | 30,700.000 | LB | REINFORCING BARS GRADE 60 | |
| 0210 | 570024 | 185.000 | L.F. | 24" CULVERT PIPE | |
| 0220 | 570036 | 22.000 | L.F. | 36" CULVERT PIPE | |
| 0230 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0240 | 601110 | 400.000 | S.Y. | REMOVAL OF SURFACING | |
| 0250 | 602000 | 6,200.000 | C.Y. | RIPRAP CLASS A | |
| 0260 | 602030 | 920.000 | C.Y. | RIPRAP CLASS D | |
| 0270 | 602040 | 1.000 | C.Y. | RIPRAP CLASS E | |
| 0280 | 602200 | 1,190.000 | C.Y. | GABIONS | |
| 0290 | 603050 | 1.000 | ALOW | CLEAN WATER ACT COMPLIANCE WORK PLAN | \$5,000.00000 |
| 0300 | 603261 | 7,700.000 | L.F. | MULCH SOCKS | |
| 0310 | 603281 | 1.000 | LS | SWPPP PLAN PREPARATION AND MAINTENANCE | |

| | | | | | |
|------|--------|-----------|------|--|----------------|
| 0320 | 606052 | 8.000 | EACH | END TREATMENT TL-2 END TERMINAL | |
| 0330 | 606062 | 8.000 | EACH | TRANSITION METAL BARRIER TO RIGID BARRIER | |
| 0340 | 606301 | 100.000 | L.F. | SINGLE FACE THRIE-BEAM WEATHERING GUARDRAIL | |
| 0350 | 607079 | 1,220.000 | L.F. | PEDESTRIAN/BICYCLE RAILING | |
| 0360 | 607506 | 2.000 | EACH | PIPE GATE 6' | |
| 0370 | 614006 | 200.000 | L.F. | PIPE CASING 6" | |
| 0380 | 617000 | 1.000 | LS | VIBRATION MONITORING | |
| 0390 | 617003 | 1.000 | LS | VIDEO TAPING | |
| 0400 | 617004 | 1.000 | LS | VIBRATION RISK SURVEY | |
| 0410 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0420 | 618011 | 1.000 | LS | PUBLIC AWARENESS | \$30,000.00000 |
| 0430 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0440 | 622001 | 1.000 | EACH | FIELD LABORATORY, TYPE I | |
| 0450 | 622100 | 1.000 | EACH | SUPPLEMENTAL FIELD LABORATORY | |
| 0460 | 622200 | 1.000 | EACH | FIELD OFFICE | |
| 0470 | 623033 | 1.000 | EACH | MEDIAN DROP INLET TYPE III (URBAN) | |
| 0480 | 632000 | 2.000 | ACRE | CLASS A SEEDING | |
| 0490 | 632020 | 5.000 | ACRE | CLASS C SEEDING | |
| 0500 | 701000 | 340.000 | S.F. | PANEL SIGNS | |
| 0510 | 701100 | 840.000 | L.F. | STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS | |
| 0520 | 702610 | 3.000 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0530 | 702810 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR CONSTRUCTION | |
| 0540 | 703003 | 20.000 | EACH | OBJECT MARKER TYPE 3 | |
| 0550 | 801000 | 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0560 | 802000 | 1.000 | LS | POST CONSTRUCTION PLANS | \$3,000.00000 |

Section 0002: BRIDGE

| | | | | | |
|------|--------|------------|------|--|--|
| 0570 | 203301 | 164.000 | C.Y. | ROCK EXCAVATION | |
| 0580 | 210000 | 1,470.000 | C.Y. | EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES | |
| 0590 | 511300 | 399.000 | C.Y. | SUBSTRUCTURE CONCRETE CLASS A | |
| 0600 | 511601 | 1.000 | LS | WIND BREAK | |
| 0610 | 512003 | 198.000 | C.Y. | HIGH PERFORMANCE CONCRETE (HPD) | |
| 0620 | 531001 | 2,318.000 | S.F. | PERMANENT ANTI-GRAFFITI PROTECTIVE COATING | |
| 0630 | 540060 | 37,850.000 | LB | REINFORCING BARS GRADE 60 | |
| 0640 | 540160 | 41,610.000 | LB | EPOXY COATED REINFORCING BARS GRADE 60 | |
| 0650 | 541000 | 300.000 | LB | STRUCTURAL STEEL FOR CONCRETE BRIDGES | |
| 0660 | 543001 | 148.000 | L.F. | METAL RAILING, TYPE A32 | |
| 0670 | 543002 | 60.000 | L.F. | METAL RAILING, TYPE A42 | |
| 0680 | 564000 | 228.000 | L.F. | PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS | |

(68 Items)

Proposal A300816

Roadway Rehabilitation

Proposal information table

Date Generated: 04/29/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 33 Counties: Bernalillo
Project ID: A300816

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-------------|------|--|-------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 403705 | 5,630.000 | TON | WMA OGFC COMPLETE | |
| 0020 | 407000 | 133.000 | TON | ASPHALT MATERIAL FOR TACK COAT | |
| 0030 | 411000 | 6,150.000 | LB | HOT POURED CRACK SEALING | |
| 0040 | 414000 | 657,570.000 | SYIN | COLD MILLING (ASPHALT) | |
| 0050 | 424003 | 30,840.000 | TON | WMA SP-III COMPLETE | |
| 0060 | 533000 | 40.000 | S.Y. | REPAIR OF CONCRETE STRUCTURES | |
| 0070 | 540060 | 280.000 | LB | REINFORCING BARS GRADE 60 | |
| 0080 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0090 | 606001 | 1,087.500 | L.F. | SINGLE FACE W-BEAM GUARDRAIL | |
| 0100 | 606011 | 75.000 | L.F. | SINGLE FACE THRIE-BEAM GUARDRAIL | |
| 0110 | 606051 | 11.000 | EACH | END TREATMENT TL-3 END TERMINAL | |
| 0120 | 606053 | 5.000 | EACH | END TREATMENT W-BEAM END ANCHOR | |
| 0130 | 606054 | 1.000 | EACH | END TREATMENT THRIE-BEAM END ANCHOR | |
| 0140 | 606062 | 7.000 | EACH | TRANSITION METAL BARRIER TO RIGID BARRIER | |
| 0150 | 606542 | 160.000 | L.F. | CONCRETE WALL BARRIER 42" | |
| 0160 | 609324 | 100.000 | L.F. | CONCRETE SLOPED CURB AND GUTTER 6" X 24" | |
| 0170 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0180 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0190 | 702610 | 8.000 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0200 | 702810 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR CONSTRUCTION | |
| 0210 | 704701 | 133,000.000 | L.F. | HOT THERMOPLASTIC PAVEMENT MARKINGS 6" | |
| 0220 | 704717 | 2.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW | |
| 0230 | 704718 | 8.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW | |
| 0240 | 704720 | 5.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY) | |
| 0250 | 704735 | 11.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW | |
| 0260 | 704869 | 130.000 | EACH | PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG | |
| 0270 | 713030 | 570.000 | L.F. | LOOP DETECTOR WIRE | |

| | | | |
|------------------------|------|--|---------------|
| 0280 713300 290.000 | L.F. | DETECTOR SAW CUT | |
| 0290 721000 11,300.000 | L.F. | REMOVAL OF PAVEMENT STRIPE | |
| 0300 730100 1.000 | LS | AUTOMATIC TRAFFIC RECORDER AND AUTOMATIC VEHICLE CLASSIFICAT ION SYSTEM | |
| 0310 801000 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0320 802000 1.000 | LS | POST CONSTRUCTION PLANS | \$5,000.00000 |
| 0330 901000 1.000 | LS | CONTRACTOR PROCESS QUALITY CONTROL | |

(33 Items)

Proposal 5101200

Roadway Reconstruction, Signalization, Lighting

Proposal information table

Date Generated: 04/29/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 51 Counties: Santa Fe
Project ID: 5101200

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-----------|------|---|----------------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 203000 | 2,400.000 | C.Y. | UNCLASSIFIED EXCAVATION | |
| 0020 | 303000 | 3,575.000 | TON | BASE COURSE | |
| 0030 | 416000 | 1,370.000 | S.Y. | MINOR PAVEMENT | |
| 0040 | 511000 | 4.000 | C.Y. | STRUCTURAL CONCRETE, CLASS A | |
| 0050 | 511030 | 146.000 | C.Y. | STRUCTURAL CONCRETE, CLASS AA | |
| 0060 | 540060 | 170.000 | LB | REINFORCING BARS GRADE 60 | |
| 0070 | 570437 | 8.000 | L.F. | 24" STORM DRAIN CULVERT PIPE | |
| 0080 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0090 | 603262 | 410.000 | L.F. | COMPOSTED MULCH SOCKS | |
| 0100 | 604002 | 1,400.000 | S.Y. | GEOTEXTILE CLASS 2 | |
| 0110 | 604310 | 6,600.000 | S.Y. | GEOGRID BASE REINFORCEMENT | |
| 0120 | 606620 | 620.000 | L.F. | STATE FURNISHED CONCRETE WALL BARRIER | |
| 0130 | 607024 | 400.000 | L.F. | CHAIN LINK FENCE 4' | |
| 0140 | 608004 | 1,200.000 | S.Y. | CONCRETE SIDEWALK 4" | |
| 0150 | 608108 | 20.000 | S.Y. | DRIVE PAD 8" | |
| 0160 | 609200 | 260.000 | L.F. | HEADER CURB | |
| 0170 | 609424 | 735.000 | L.F. | CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24" | |
| 0180 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0190 | 618011 | 1.000 | LS | PUBLIC AWARENESS | \$10,000.00000 |
| 0200 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0210 | 623321 | 1.000 | EACH | CURB DROP INLET TYPE I-A, OVER 4' | |
| 0220 | 662400 | 2.000 | EACH | MANHOLE ADJUSTMENT | |
| 0230 | 663049 | 1.000 | LS | PRECONSTRUCTION UTILITY SURVEY | |
| 0240 | 663850 | 2.000 | EACH | WATER VALVE ADJUSTMENT | |
| 0250 | 702810 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR CONSTRUCTION | |
| 0260 | 702811 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR PEDESTRIAN AND BICYCLIST | |
| 0270 | 704000 | 9,800.000 | L.F. | RETROREFLECTORIZED PAINTED MARKINGS 4" | |
| 0280 | 704701 | 2,000.000 | L.F. | HOT THERMOPLASTIC PAVEMENT MARKINGS 6" | |
| 0290 | 704715 | 1.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING COMBINATION (THRU AND RIGH T) ARROW | |

| | | | | | |
|------|--------|-----------|-------|---|---------------|
| 0300 | 704717 | 4.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW | |
| 0310 | 704718 | 4.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW | |
| 0320 | 704719 | 6.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING THRU ARROW | |
| 0330 | 704720 | 5.000 | EACH | HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY) | |
| 0340 | 705000 | 1.000 | ALLOW | SIGNAL/LIGHTING SYSTEM START-UP COSTS | \$1,000.00000 |
| 0350 | 707801 | 2.000 | EACH | REMOVE & RESET TYPE I STANDARD COMPLETE | |
| 0360 | 707810 | 1.000 | EACH | REMOVE & RESET LIGHTING STANDARD & LUMINAIRE | |
| 0370 | 709020 | 860.000 | L.F. | RIGID ELECTRICAL CONDUIT 2" (DIA.) | |
| 0380 | 709030 | 270.000 | L.F. | RIGID ELECTRICAL CONDUIT 3" (DIA.) | |
| 0390 | 710000 | 5.000 | EACH | ELECTRICAL PULL BOX (STANDARD) | |
| 0400 | 710010 | 8.000 | EACH | ELECTRICAL PULL BOX (LARGE) | |
| 0410 | 711005 | 1,500.000 | L.F. | MULTI CONDUCTOR CABLE 5 | |
| 0420 | 711007 | 50.000 | L.F. | MULTI CONDUCTOR CABLE 7 | |
| 0430 | 711012 | 450.000 | L.F. | MULTI CONDUCTOR CABLE 12 | |
| 0440 | 711104 | 1,180.000 | L.F. | SINGLE CONDUCTOR 4 | |
| 0450 | 712501 | 8.000 | EACH | ACCESSIBLE PEDESTRIAN SIGNAL | |
| 0460 | 713600 | 300.000 | L.F. | OPTICAL DETECTOR CABLE | |
| 0470 | 713806 | 720.000 | L.F. | VIDEO POWER CABLE | |
| 0480 | 720060 | 1.000 | EACH | VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES | |
| 0490 | 721000 | 870.000 | L.F. | REMOVAL OF PAVEMENT STRIPE | |
| 0500 | 801000 | 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0510 | 802000 | 1.000 | LS | POST CONSTRUCTION PLANS | \$5,000.00000 |

(51 Items)