

Proposal 11013301101331

Roadway Rehabilitation

Proposal information table

Date Generated: 06/15/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 30 Counties: Luna
Project ID: 1101330

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	404010	11,826.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0020	407000	250.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	407001	190.000	TON	FOG SEAL	
0040	410305	52,704.000	TON	STOCKPILED SURFACE TREATMENT AGGREGATE 3/8"	
0050	414000	1,264,890.000	SYIN	COLD MILLING (ASPHALT)	
0060	417100	1,758.000	L.F.	ASPHALT CURB	
0070	423282	58,156.000	TON	HMA SP-III COMPLETE	
0080	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0090	606001	4,512.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0100	606051	52.000		EACH END TREATMENT TL-3 END TERMINAL	
0110	606055	2.000		EACH END TREATMENT DRIVEWAY END ANCHOR	
0120	606061	1,012.500	L.F.	DRAINAGE STRUCTURE PROTECTION SYSTEM	
0130	606062	32.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0140	606542	827.000	L.F.	CONCRETE WALL BARRIER 42"	
0150	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0160	620000	3.000	ACRE	SELECTIVE/NON-SELECTIVE HERBICIDE APPLICATION	
0170	621000	1.000	LS	MOBILIZATION	
0180	702000	1,170.000	S.F.	CONSTRUCTION SIGNING	
0190	702100	1,930.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0200	702110	40.000		EACH PORTABLE SIGN SUPPORT	
0210	702238	2.000		EACH BARRICADE, TYPE III-8'	
0220	702525	310.000		EACH CHANNELIZATION DEVICES TYPE DRUM	
0230	702610	10.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0240	704000	977,169.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0250	704876	29,520.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
0260	720100	17.000		EACH SAND BARREL VEHICULAR IMPACT ATTENUATOR	

UNIT

0270 720110 15.000	EACH REMOVE/RESET IMPACT ATTENUATOR UNIT	
0280 801000 1.000	LS CONSTRUCTION STAKING BY THE CONTRACTOR	
0290 802000 1.000	LS POST CONSTRUCTION PLANS	\$3,000.00000
0300 901000 1.000	LS CONTRACTOR PROCESS QUALITY CONTROL	

(30 Items)

Proposal 4100381

Roadway Reconstruction and Bridge Replacement

Proposal information table

Date Generated: 06/15/2016 Sections: 2
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 101 Counties: Mora
Project ID: 4100381

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	34,800.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	6,700.000	C.Y.	BORROW	
0040	203200	500.000	C.Y.	SUBEXCAVATION	
0050	203211	1,100.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0060	203301	500.000	C.Y.	ROCK EXCAVATION	
0070	207000	44,990.000	S.Y.	SUBGRADE PREPARATION	
0080	302000	21,860.000	S.Y.	PROCESSING, PLACING AND COMPACTING EXISTING PAVEMENT	
0090	303000	9,450.000	TON	BASE COURSE	
0100	405000	4,920.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0110	407000	25.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0120	408100	73.000	TON	PRIME COAT MATERIAL	
0130	417000	2,930.000	S.Y.	MISCELLANEOUS PAVING	
0140	424003	11,130.000	TON	WMA SP-III COMPLETE	
0150	506010	17,074.000	S.F.	SOIL NAIL RETAINING WALL	
0160	506011	17,921.000	L.F.	PERMANENT SOIL NAILS	
0170	506012	9.000	EACH	VERIFICATION TEST NAILS	
0180	516000	60.000	C.Y.	FLOWABLE FILL	
0190	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0200	570024	1,100.000	L.F.	24" CULVERT PIPE	
0210	570025	26.000	EACH	24" CULVERT PIPE END SECTION	
0220	570036	40.000	L.F.	36" CULVERT PIPE	
0230	570162	70.000	L.F.	42"SX29"R (NOMINAL) CULVERT PIPE ARCH	
0240	570163	2.000	EACH	42"SX29"R (NOMINAL) CULVERT PIPE ARCH END SECTION	
0250	570164	100.000	L.F.	49"SX33"R (NOMINAL) CULVERT PIPE ARCH	
0260	570165	4.000	EACH	49"SX33"R (NOMINAL) CULVERT PIPE ARCH END SECTION	
0270	571578	129.000	L.F.	14'10"S x 4'-10"R METAL BOX CULVERT	
0280	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	

0290	602000	260.000	C.Y.	RIPRAP CLASS A	
0300	602010	320.000	C.Y.	RIPRAP CLASS B	
0310	602200	670.000	C.Y.	GABIONS	
0320	603050	1.000	ALOW	CLEAN WATER ACT COMPLIANCE WORK PLAN	\$10,000.00000
0330	603220	280.000	L.F.	CHECK DAM TYPE I	
0340	603250	20.000	EACH	DROP INLET PROTECTION TYPE I	
0350	603262	9,820.000	L.F.	COMPOSTED MULCH SOCKS	
0360	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0370	604001	539.000	S.Y.	GEOTEXTILE CLASS 1	
0380	606001	1,620.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0390	606011	530.000	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0400	606052	19.000	EACH	END TREATMENT TL-2 END TERMINAL	
0410	606055	2.000	EACH	END TREATMENT DRIVEWAY END ANCHOR	
0420	606062	9.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0430	606532	240.000	L.F.	CONCRETE WALL BARRIER 32"	
0440	606595	1,300.000	L.F.	CONCRETE WALL BARRIER (HALF SECTION)	
0450	606619	1,350.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0460	606620	1,100.000	L.F.	STATE FURNISHED CONCRETE WALL BARRIER	
0470	607004	27,570.000	L.F.	BARBED WIRE FENCE 4'	
0480	607012	4,633.000	L.F.	GAME FENCE	
0490	607312	5.000	EACH	STANDARD GATE, 12'	
0500	607316	17.000	EACH	STANDARD GATE, 16'	
0510	607455	3.000	EACH	CHAIN LINK GATE, 8' S X 8' R	
0520	610024	3.000	EACH	CATTLE GUARD 24'	
0530	610036	1.000	EACH	CATTLE GUARD 36'	
0540	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0550	618011	1.000	LS	PUBLIC AWARENESS	\$7,500.00000
0560	621000	1.000	LS	MOBILIZATION	
0570	622002	1.000	EACH	FIELD LABORATORY, TYPE II	
0580	622100	1.000	EACH	SUPPLEMENTAL FIELD LABORATORY	
0590	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	
0600	623011	9.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=0'0" TO 3'0"	
0610	623013	1.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=6'1" TO 9'0"	
0620	623014	1.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=9'1" TO 12'0"	
0630	623015	6.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=12'1" TO 15'0"	
0640	623410	2.000	EACH	DROP INLET SPECIAL DESIGN	
0650	624100	540.000	S.Y.	SLOPE PROTECTION WIRE MESH PVC COATED	
0660	624200	490.000	L.F.	RESIN GROUTED STEEL BOLTS	
0670	624300	180.000	L.F.	RESIN GROUTED STEEL ANCHORS	
0680	626000	540.000	S.Y.	SCALING OF ROCK SLOPES	
0690	632000	13.000	ACRE	CLASS A SEEDING	

0700	632100	2.000	ACRE	STEEP SLOPE SEEDING	
0710	701000	310.000	S.F.	PANEL SIGNS	
0720	701100	720.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0730	702610	4.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0740	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0750	703002	53.000	EACH	OBJECT MARKER TYPE 2	
0760	704000	101,000.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0770	704101	4.000	EACH	TEMPORARY WORD OR SYMBOL	
0780	720060	4.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0790	720110	4.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0800	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0810	802000	1.000	LS	POST CONSTRUCTION PLANS	\$10,000.00000

Section 0002: BRIDGE

0820	210000	1,157.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0830	503000	3,861.000	L.F.	MICROPILE	
0840	503001	3,018.000	L.F.	MICROPILE PERMANENT CASING	
0850	503002	40.000	L.F.	UNEXPECTED OBSTRUCTION DRILLING	
0860	503003	4.000	EACH	MICROPILE VERIFICATION LOAD TEST	
0870	503004	8.000	EACH	MICROPILE PROOF LOAD TEST	
0880	511300	158.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
0890	511601	1.000	LS	WIND BREAK	
0900	511602	1.000	LS	FOGGING SYSTEM	
0910	512003	333.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0920	516000	262.000	C.Y.	FLOWABLE FILL	
0930	518045	810.000	L.F.	PRESTRESSED CONCRETE BRIDGE MEMBER TYPE 45	
0940	540060	14,920.000	LB	REINFORCING BARS GRADE 60	
0950	540160	59,480.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0960	541000	6,480.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
0970	543001	462.000	L.F.	METAL RAILING, TYPE A32	
0980	562000	138.000	L.F.	BRIDGE JOINT STRIP SEAL	
0990	564000	130.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
1000	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
1010	602000	370.000	C.Y.	RIPRAP CLASS A	

(101 Items)

Proposal 6100828

Bridge Rehabilitation

Proposal information table

Date Generated: 06/15/2016 Sections: 2
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 12 Counties: Sandoval
Project ID: 6100828

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	512000	26.000	C.Y.	SUPERSTRUCTURE CONCRETE	
0020	535100	8,003.000	S.Y.	CONCRETE SURFACE TREATMENT	
0030	536001	8,090.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
0040	540160	4,260.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0050	562000	391.000	L.F.	BRIDGE JOINT STRIP SEAL	
0060	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0070	621000	1.000	LS	MOBILIZATION	
Section 0002: CONSTRUCTION ENGINEERING					
0080	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0090	702610	2.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0100	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0110	704000	190,100.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0120	802000	1.000	LS	POST CONSTRUCTION PLANS	\$3,000.00000

(12 Items)

Proposal 9900705

Lighting

Proposal information table

Date Generated: 06/16/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 004 Highway Number:
Items: 25 Counties: Sierra
Project ID: 9900705

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: LIGHTING					
0010	502030	150.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0020	540060	3,749.000	LB	REINFORCING BARS GRADE 60	
0030	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0040	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0050	621000	1.000	LS	MOBILIZATION	
0060	702000	873.000	S.F.	CONSTRUCTION SIGNING	
0070	702100	803.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0080	702110	27.000	EACH	PORTABLE SIGN SUPPORT	
0090	702238	2.000	EACH	BARRICADE, TYPE III-8'	
0100	702525	50.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0110	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0120	705000	1.000		ALLOW SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$3,000.00000
0130	706010	1.000	EACH	SERVICE POLE (LIGHTING)	
0140	706110	1.000	EACH	SERVICE RISER (LIGHTING)	
0150	706350	1.000	LS	POWER SERVICE INSTALLATION	\$2,000.00000
0160	706405	1.000	EACH	LIGHTING CONTROL CABINET-SIX CIRCUIT	
0170	707540	23.000	EACH	TYPE V STANDARD, 40'	
0180	709020	4,675.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0190	709030	55.000	L.F.	RIGID ELECTRICAL CONDUIT 3" (DIA.)	
0200	710000	15.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0210	711102	10,370.000	L.F.	SINGLE CONDUCTOR 2	
0220	711210	180.000	L.F.	SINGLE CONDUCTOR 1/0	
0230	716701	23.000	EACH	LED ROADWAY LUMINAIRE	
0240	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0250	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000

(25 Items)

Proposal 9900714

Safety (Guardrail Installation and Concrete Wall Barrier)

Proposal information table

Date Generated: 06/15/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 005 Highway Number:
Items: 17 Counties: Guadalupe
Project ID: 9900714

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203000	310.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	203100	310.000	C.Y.	BORROW	
0030	207000	460.000	S.Y.	SUBGRADE PREPARATION	
0040	208000	0.200	MILE	LINEAR GRADING	
0050	303010	75.000	C.Y.	BASE COURSE	
0060	417000	375.000	S.Y.	MISCELLANEOUS PAVING	
0070	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0080	603262	100.000	L.F.	COMPOSTED MULCH SOCKS	
0090	606011	50.000	L.F.	SINGLE FACE THRIE-BEAM GUARDRAIL	
0100	606051	1.000		EACH END TREATMENT TL-3 END TERMINAL	
0110	606062	1.000		EACH TRANSITION METAL BARRIER TO RIGID BARRIER	
0120	606542	400.000	L.F.	CONCRETE WALL BARRIER 42"	
0130	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0140	621000	1.000	LS	MOBILIZATION	
0150	702610	3.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0160	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0170	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	

(17 Items)