

Proposal 1100570

Roadway Rehabilitation

Proposal information table

Date Generated: 07/20/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 26 Counties: Dona Ana
Project ID: 1100570

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	404010	11,205.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0020	407000	295.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	407001	36.000	TON	FOG SEAL	
0040	408100	85.000	TON	PRIME COAT MATERIAL	
0050	410305	63,384.000	TON	STOCKPILED SURFACE TREATMENT AGGREGATE 3/8"	
0060	414000	1,609,850.000	SYIN	COLD MILLING (ASPHALT)	
0070	417000	44,210.000	S.Y.	MISCELLANEOUS PAVING	
0080	423283	71,260.000	TON	HMA SP-IV COMPLETE	
0090	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0100	621000	1.000	LS	MOBILIZATION	
0110	631000	181,000.000	L.F.	RUMBLE STRIPS	
0120	702000	1,510.000	S.F.	CONSTRUCTION SIGNING	
0130	702100	700.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0140	702110	66.000	EACH	PORTABLE SIGN SUPPORT	
0150	702525	600.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0160	702600	2.000	EACH	SEQUENTIAL ARROW DISPLAY	
0170	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0180	702613	2.000	EACH	SPEED DETECTOR RADAR TRAILER	
0190	704000	829,000.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0200	704099	273,050.000	L.F.	TEMPORARY STRIPING	
0210	704701	1,140.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0220	704735	11.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
0230	704869	70.000	EACH	PLOWABLE REFLECTIVE RAISED PAVEMENT MARKER TYPE PG	
0240	704876	9,150.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
0250	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0260	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(26 Items)

Proposal 2101880

Bridge Rehabilitation

Proposal information table

Date Generated: 07/20/2016 Sections: 2
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 23 Counties: Chaves
Project ID: 2101880

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	411000	54.000	LB	HOT POURED CRACK SEALING	
0020	530300	600.000	LB	REPLACEMENT REINFORCING BARS GRADE 60	
0030	533000	124.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0040	534000	20.000	GAL	EPOXY INJECTION, TYPE I	
0050	535100	8.000	S.Y.	CONCRETE SURFACE TREATMENT	
0060	541000	1,205.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
0070	546000	1.000	LS	RECOATING STRUCTURES	
0080	546200	314.000	S.F.	SP 3 POWER TOOL CLEANING	
0090	546210	2,757.000	S.F.	SP 11 POWER TOOL CLEANING	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
Section 0002: CONSTRUCTION SIGNING					
0110	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0120	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0130	618011	1.000	LS	PUBLIC AWARENESS	\$5,000.00000
0140	621000	1.000	LS	MOBILIZATION	
0150	702000	450.000	S.F.	CONSTRUCTION SIGNING	
0160	702100	270.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0170	702110	20.000		EACH PORTABLE SIGN SUPPORT	
0180	702238	2.000		EACH BARRICADE, TYPE III-8'	
0190	702320	30.000		EACH VERTICAL PANEL, TYPE BACK TO BACK	
0200	702610	3.000		EACH PORTABLE CHANGEABLE MESSAGE SIGN	
0210	704000	60,960.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0220	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0230	802000	1.000	LS	POST CONSTRUCTION PLANS	\$3,000.00000

(23 Items)

Proposal 2100372

Drainage Improvements

Proposal information table

Date Generated: 07/20/2016 Sections: 2
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 16 Counties: Otero
Project ID: 2100372

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	511000	45.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0020	516000	600.000	C.Y.	FLOWABLE FILL	
0030	533000	40.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0040	540060	4,740.000	LB	REINFORCING BARS GRADE 60	
0050	570479	1,102.000	L.F.	54" STORM DRAIN CULVERT PIPE	
0060	570493	58.000	L.F.	66" STORM DRAIN CULVERT PIPE	
0070	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
Section 0002: ROADWAY					
0080	201000	1.000	LS	CLEARING AND GRUBBING	
0090	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0100	603262	150.000	L.F.	COMPOSTED MULCH SOCKS	
0110	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0120	621000	1.000	LS	MOBILIZATION	
0130	702000	554.000	S.F.	CONSTRUCTION SIGNING	
0140	702100	668.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0150	702110	12.000	EACH	PORTABLE SIGN SUPPORT	
0160	802000	1.000	LS	POST CONSTRUCTION PLANS	\$3,000.00000
(16 Items)					

Proposal 9900717

Safety (High Friction Surface Treatment)

Proposal information table

Date Generated: 07/20/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 004 Highway Number:
Items: 8 Counties: McKinley
Project ID: 9900717

Not available for contractor viewing until 07/22/2016.

Not yet available for contractor viewing.

[Export \(csv\)](#) | [Export \(tab\)](#)

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	409000	14,850.000	S.Y.	HIGH FRICTION SURFACE TREATMENT	
0020	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0030	621000	1.000	LS	MOBILIZATION	
0040	702610	3.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0050	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0060	704701	12,000.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0070	721000	12,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0080	802000	1.000	LS	POST CONSTRUCTION PLANS	\$2,000.00000
(8 Items)					