

# Proposal 2101290

## Roadway Rehabilitation

### Proposal information table

Date Generated: 08/18/2016 Sections: 1  
Date Revised: Amendments: 0  
Call Order: 001 Highway Number:  
Items: 20 Counties: Eddy  
Project ID: 2101290

### Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	404010	4,486.000	TON	RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC)	
0020	407000	119.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0030	414000	589,300.000	SYIN	COLD MILLING (ASPHALT)	
0040	423282	27,820.000	TON	HMA SP-III COMPLETE	
0050	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0060	618011	1.000	LS	PUBLIC AWARENESS	\$10,000.00000
0070	621000	1.000	LS	MOBILIZATION	
0080	631000	92,450.000	L.F.	RUMBLE STRIPS	
0090	702000	620.000	S.F.	CONSTRUCTION SIGNING	
0100	702100	380.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0110	702110	28.000	EACH	PORTABLE SIGN SUPPORT	
0120	702238	1.000	EACH	BARRICADE, TYPE III-8'	
0130	702525	304.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0140	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0150	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$35,000.00000
0160	704099	140,400.000	L.F.	TEMPORARY STRIPING	
0170	704700	140,400.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0180	704875	4,950.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TD	
0190	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0200	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	

(20 Items)

# Proposal 4101090R

Fencing (Game Fence) and Signalization

Proposal information table

Date Generated: 08/18/2016 Sections: 1  
Date Revised: Amendments: 0  
Call Order: 002 Highway Number:  
Items: 18 Counties: Colfax  
Project ID: 4101090R

Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	203000	980.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	511000	4.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0030	540060	119.000	LB	REINFORCING BARS GRADE 60	
0040	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0050	607012	47,634.000	L.F.	GAME FENCE	
0060	607013	24.000	EACH	GAME ESCAPE RAMP	
0070	607455	2.000	EACH	CHAIN LINK GATE, 8' S X 8' R	
0080	607951	234.000	L.F.	ELECTRIFIED BARRIER	
0090	610080	121.000	L.F.	GAME GUARD	
0100	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0110	618011	1.000	LS	PUBLIC AWARENESS	\$5,000.00000
0120	621000	1.000	LS	MOBILIZATION	
0130	701000	184.000	S.F.	PANEL SIGNS	
0140	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0150	707018	7.000	EACH	TYPE I STANDARD, 18'	
0160	712011	14.000	EACH	1 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
0170	715110	7.000	EACH	FLASHER CONTROLLER WITH TIME CLOCK	
0180	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	

(18 Items)

# Proposal 9900713

Safety (Scaling of Rock Slopes and

## Proposal information table

Date Generated: 08/18/2016 Sections: 1  
 Date Revised: Amendments: 0  
 Call Order: 003 Highway Number:  
 Items: 24 Counties: Otero  
 Project ID: 9900713

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	203000	2,000.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	203301	2,000.000	C.Y.	ROCK EXCAVATION	
0030	603262	2,105.000	L.F.	COMPOSTED MULCH SOCKS	
0040	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0050	606542	1,030.000	L.F.	CONCRETE WALL BARRIER 42"	
0060	606600	1,030.000	L.F.	TEMPORARY CWB RETAINED BY THE DEPARTMENT	
0070	606610	200.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0080	606619	1,860.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0090	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0100	618011	1.000	LS	PUBLIC AWARENESS	\$5,000.00000
0110	621000	1.000	LS	MOBILIZATION	
0120	626000	11,680.000	S.Y.	SCALING OF ROCK SLOPES	
0130	701031	13.000	EACH	REMOVE AND RESET TRAFFIC SIGN	
0140	702000	608.000	S.F.	CONSTRUCTION SIGNING	
0150	702100	763.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0160	702110	19.000	EACH	PORTABLE SIGN SUPPORT	
0170	702238	1.000	EACH	BARRICADE, TYPE III-8'	
0180	702525	74.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0190	702610	5.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0200	704000	117,681.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0210	720050	2.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT	
0220	720060	2.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0230	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0240	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000

(24 Items)

# Proposal 9900712

Safety (Lighting)

## Proposal information table

Date Generated: 08/18/2016 Sections: 1  
Date Revised: Amendments: 0  
Call Order: 004 Highway Number:  
Items: 23 Counties: Eddy  
Project ID: 9900712

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	502030	145.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0020	511000	2.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0030	540060	3,590.000	LB	REINFORCING BARS GRADE 60	
0040	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0050	621000	1.000	LS	MOBILIZATION	
0060	702000	372.000	S.F.	CONSTRUCTION SIGNING	
0070	702100	640.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0080	702110	8.000		EACH PORTABLE SIGN SUPPORT	
0090	702525	42.000		EACH CHANNELIZATION DEVICES TYPE DRUM	
0100	704320	4.000		EACH RETROREFLECTORIZED PLASTIC RIGHT ARROW	
0110	704330	4.000		EACH RETROREFLECTORIZED PLASTIC LEFT ARROW	
0120	704340	2.000		EACH RETROREFLECTORIZED PLASTIC THRU ARROW	
0130	704400	4.000		EACH RETROREFLECTORIZED PLASTIC WORD (ONLY)	
0140	706110	2.000		EACH SERVICE RISER (LIGHTING)	
0150	706350	1.000	LS	POWER SERVICE INSTALLATION	\$2,731.00000
0160	706420	2.000		EACH LIGHTING CONTROL CABINET-TWO CIRCUIT	
0170	707540	22.000		EACH TYPE V STANDARD, 40'	
0180	709020	5,340.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0190	710000	11.000		EACH ELECTRICAL PULL BOX (STANDARD)	
0200	711102	5,400.000	L.F.	SINGLE CONDUCTOR 2	
0210	716701	22.000		EACH LED ROADWAY LUMINAIRE	
0220	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0230	802000	1.000	LS	POST CONSTRUCTION PLANS	\$4,000.00000

(23 Items)

# Proposal 6100850

Roadway Reconstruction, Signalization and Lighting

## Proposal information table

Date Generated: 08/25/2016 Sections: 1  
Date Revised: Amendments: 0  
Call Order: 005 Highway Number:  
Items: 106 Counties: McKinley  
Project ID: 6100850

## Proposal items table

Line	Item	Quantity	Unit	Description	Price
<b>Section 0001: ROADWAY</b>					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	150.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	850.000	C.Y.	BORROW	
0040	203211	300.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0050	203301	30.000	C.Y.	ROCK EXCAVATION	
0060	206000	35.000	C.Y.	UNSUITABLE MATERIAL EXCAVATION	
0070	207000	2,580.000	S.Y.	SUBGRADE PREPARATION	
0080	303000	1,550.000	TON	BASE COURSE	
0090	407001	23.000	TON	FOG SEAL	
0100	416000	2,860.000	S.Y.	MINOR PAVEMENT	
0110	502030	272.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0120	502036	96.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0130	506009	2,280.000	S.F.	GRAVITY BLOCK WALL	
0140	511000	461.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0150	540060	75,175.000	LB	REINFORCING BARS GRADE 60	
0160	570192	48.000	L.F.	128" SX83" R (NOMINAL) CULVERT PIPE ARCH	
0170	570425	10.000	L.F.	18" STORM DRAIN CULVERT PIPE	
0180	570437	80.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0190	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0200	601110	2,640.000	S.Y.	REMOVAL OF SURFACING	
0210	602000	2.000	C.Y.	RIPRAP CLASS A	
0220	603100	0.500	ACRE	TEMPORARY SOIL STABILANT	
0230	603261	2,000.000	L.F.	MULCH SOCKS	
0240	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0250	606001	413.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0260	606052	2.000	EACH	END TREATMENT TL-2 END TERMINAL	
0270	606062	4.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0280	607004	30.000	L.F.	BARBED WIRE FENCE 4'	
0290	607026	140.000	L.F.	CHAIN LINK FENCE 6'	
0300	607079	22.000	L.F.	PEDESTRIAN/BICYCLE RAILING	

0310	608004	2,500.000	S.Y.	CONCRETE SIDEWALK 4"	
0320	608106	10.000	S.Y.	DRIVE PAD 6"	
0330	609200	330.000	L.F.	HEADER CURB	
0340	609424	4,900.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	
0350	609478	160.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	
0360	609636	200.000	L.F.	CONCRETE VALLEY GUTTER 6" X 36"	
0370	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0380	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0390	618011	1.000	LS	PUBLIC AWARENESS	\$8,000.00000
0400	621000	1.000	LS	MOBILIZATION	
0410	623004	1.000	EACH	MEDIAN DROP INLET TYPE I (URBAN) H=6'1" TO 9'0"	
0420	623311	2.000	EACH	CURB DROP INLET TYPE I-B, 0' TO 4'	
0430	623331	1.000	EACH	CURB DROP INLET TYPE I-B, OVER 4'	
0440	623600	1.000	EACH	JUNCTION BOX	
0450	632000	0.400	ACRE	CLASS A SEEDING	
0460	662000	1.000	EACH	MANHOLE TYPE C-4' DIAMETER 0' TO 6' DEPTH	
0470	701000	340.000	S.F.	PANEL SIGNS	
0480	701030	4.000	EACH	REMOVE AND RESET PANEL SIGN	
0490	701100	745.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0500	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0510	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0520	702811	1.000	LS	TRAFFIC CONTROL DEVICES FOR PEDESTRIAN AND BICYCLIST	
0530	704700	21,470.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0540	704701	16,280.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0550	704717	14.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0560	704718	22.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0570	704720	15.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0580	704732	20.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING BIKE SYMBOL (BIKEWAY)	
0590	704734	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING SHARROW SYMBOL	
0600	705000	1.000	ALOW	SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$10,000.00000
0610	706100	2.000	EACH	SERVICE RISER (SIGNAL)	
0620	706110	3.000	EACH	SERVICE RISER (LIGHTING)	
0630	706350	1.000	LS	POWER SERVICE INSTALLATION	\$20,000.00000
0640	706420	3.000	EACH	LIGHTING CONTROL CABINET-TWO CIRCUIT	
0650	707004	1.000	EACH	TYPE I STANDARD, 4'	

0660	707013	2.000	EACH	TYPE I STANDARD, 13'
0670	707015	13.000	EACH	TYPE I STANDARD, 15'
0680	707018	2.000	EACH	TYPE I STANDARD, 18'
0690	707220	1.000	EACH	TYPE II STANDARD, 20' ARM
0700	707225	2.000	EACH	TYPE II STANDARD, 25' ARM
0710	707230	1.000	EACH	TYPE II STANDARD, 30' ARM
0720	707320	1.000	EACH	TYPE III STANDARD, 20' ARM
0730	707330	1.000	EACH	TYPE III STANDARD, 30' ARM
0740	707525	12.000	EACH	TYPE V STANDARD, 25'
0750	707530	35.000	EACH	TYPE V STANDARD, 30'
0760	709020	7,780.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)
0770	709030	3,295.000	L.F.	RIGID ELECTRICAL CONDUIT 3" (DIA.)
0780	710000	5.000	EACH	ELECTRICAL PULL BOX (STANDARD)
0790	710010	21.000	EACH	ELECTRICAL PULL BOX (LARGE)
0800	711005	3,245.000	L.F.	MULTI CONDUCTOR CABLE 5
0810	711007	180.000	L.F.	MULTI CONDUCTOR CABLE 7
0820	711020	2,540.000	L.F.	MULTI CONDUCTOR CABLE 20
0830	711102	13,200.000	L.F.	SINGLE CONDUCTOR 2
0840	711106	1,460.000	L.F.	SINGLE CONDUCTOR 6
0850	711108	1,460.000	L.F.	SINGLE CONDUCTOR 8
0860	711512	2,000.000	L.F.	COMMUNICATION CABLE 12 PAIR
0870	712031	22.000	EACH	3 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)
0880	712051	17.000	EACH	5 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)
0890	712201	20.000	EACH	PEDESTRIAN SIGNAL (LED)
0900	712330	10.000	EACH	3 SECTION BACKPLATE
0910	712350	7.000	EACH	5 SECTION BACKPLATE
0920	713020	19.000	EACH	PUSH BUTTON STATION
0930	713410	2.000	EACH	PHASE SELECTOR RACK, 1 CHANNEL
0940	713430	6.000	EACH	PHASE SELECTOR MODULE
0950	713511	6.000	EACH	OPTICAL DETECTOR, 1 DIRECTION, 1 CHANNEL
0960	713600	1,205.000	L.F.	OPTICAL DETECTOR CABLE
0970	713807	1,275.000	L.F.	VIDEO CABLE
0980	713810	6.000	EACH	VIDEO CAMERA
0990	713825	2.000	EACH	VIDEO HARDWARE SYSTEM
1000	714000	2.000	EACH	TRAFFIC ACTUATED CONTROLLER
1010	714280	2.000	EACH	8 PHASE DOUBLE RING CONTROLLER CABINET
1020	716700	47.000	EACH	LUMINAIRE TYPE LED
1030	720050	2.000	EACH	PERMANENT VEHICULAR IMPACT ATTENUATOR UNIT
1040	721000	28,500.000	L.F.	REMOVAL OF PAVEMENT STRIPE
1050	721101	13.000	EACH	REMOVAL OF PAVEMENT MARKING
1060	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR

**(106 Items)**