

Proposal 2102100

Roadway Rehabilitation

Proposal information table

Date Generated: 09/21/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 001 Highway Number:
Items: 35 Counties: Lea
Project ID: 2102100

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-------------|------|---|-------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 301012 | 182,229.000 | S.Y. | FULL DEPTH RECLAMATION - FOAMED ASPHALT STABILIZED BASE | |
| 0020 | 301014 | 2,623.000 | TON | ASPHALT BINDER | |
| 0030 | 301015 | 1,124.000 | TON | MINERAL FILLER | |
| 0040 | 303015 | 759.000 | S.Y. | BASE COURSE | |
| 0050 | 404010 | 6,193.000 | TON | RUBBERIZED OPEN GRADED FRICTION COURSE COMPLETE (ROGFC) | |
| 0060 | 407000 | 171.000 | TON | ASPHALT MATERIAL FOR TACK COAT | |
| 0070 | 414000 | 3,900.000 | SYIN | COLD MILLING (ASPHALT) | |
| 0080 | 416000 | 394.000 | S.Y. | MINOR PAVEMENT | |
| 0090 | 423282 | 49,167.000 | TON | HMA SP-III COMPLETE | |
| 0100 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0110 | 606001 | 300.000 | L.F. | SINGLE FACE W-BEAM GUARDRAIL | |
| 0120 | 606051 | 4.000 | | EACH END TREATMENT TL-3 END TERMINAL | |
| 0130 | 606062 | 4.000 | | EACH TRANSITION METAL BARRIER TO RIGID BARRIER | |
| 0140 | 606542 | 84.000 | L.F. | CONCRETE WALL BARRIER 42" | |
| 0150 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0160 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0170 | 631000 | 134,734.000 | L.F. | RUMBLE STRIPS | |
| 0180 | 701000 | 1,050.000 | S.F. | PANEL SIGNS | |
| 0190 | 701100 | 3,200.000 | L.F. | STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS | |
| 0200 | 702000 | 800.000 | S.F. | CONSTRUCTION SIGNING | |
| 0210 | 702100 | 930.000 | L.F. | STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING | |
| 0220 | 702110 | 34.000 | | EACH PORTABLE SIGN SUPPORT | |
| 0230 | 702238 | 1.000 | | EACH BARRICADE, TYPE III-8' | |
| 0240 | 702525 | 262.000 | | EACH CHANNELIZATION DEVICES TYPE DRUM | |
| 0250 | 702599 | 198.000 | L.F. | TEMPORARY PORTABLE RUMBLE STRIPS | |
| 0260 | 702610 | 5.000 | | EACH PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0270 | 704000 | 607,800.000 | L.F. | RETROREFLECTORIZED PAINTED MARKINGS 4" | |

| | | | | | |
|------|--------|-------------|------|---|---------------|
| 0280 | 704099 | 202,600.000 | L.F. | TEMPORARY STRIPING | |
| 0290 | 704875 | 2,092.000 | EACH | TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TD | |
| 0300 | 704876 | 3,396.000 | EACH | TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG | |
| 0310 | 720100 | 2.000 | EACH | SAND BARREL VEHICULAR IMPACT ATTENUATOR UNIT | |
| 0320 | 720110 | 2.000 | EACH | REMOVE/RESET IMPACT ATTENUATOR UNIT | |
| 0330 | 801000 | 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0340 | 802000 | 1.000 | LS | POST CONSTRUCTION PLANS | \$5,000.00000 |
| 0350 | 901000 | 1.000 | LS | CONTRACTOR PROCESS QUALITY CONTROL | |

(35 Items)

Proposal 6100640

Roadway Rehabilitation

Proposal information table

Date Generated: 09/21/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 002 Highway Number:
Items: 33 Counties: Cibola
Project ID: 6100640

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-------------|------|---|-------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 203100 | 8,000.000 | C.Y. | BORROW | |
| 0020 | 203211 | 100.000 | S.Y. | UNSTABLE SUBGRADE STABILIZATION | |
| 0030 | 403701 | 3,170.000 | TON | OPEN GRADED FRICTION COURSE COMPLETE | |
| 0040 | 405000 | 7,700.000 | S.Y. | DETOUR PAVEMENT CONSTRUCTION | |
| 0050 | 407000 | 91.000 | TON | ASPHALT MATERIAL FOR TACK COAT | |
| 0060 | 415000 | 135,200.000 | S.Y. | PAVEMENT SURFACE RESTORATION | |
| 0070 | 423282 | 44,480.000 | TON | HMA SP-III COMPLETE | |
| 0080 | 570012 | 1,400.000 | L.F. | 12" CULVERT PIPE | |
| 0090 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0100 | 603100 | 0.800 | ACRE | TEMPORARY SOIL STABILANT | |
| 0110 | 606001 | 9,113.000 | L.F. | SINGLE FACE W-BEAM GUARDRAIL | |
| 0120 | 606011 | 188.000 | L.F. | SINGLE FACE THRIE-BEAM GUARDRAIL | |
| 0130 | 606051 | 12.000 | | EACH END TREATMENT TL-3 END TERMINAL | |
| 0140 | 606053 | 11.000 | | EACH END TREATMENT W-BEAM END ANCHOR | |
| 0150 | 606054 | 1.000 | | EACH END TREATMENT THRIE-BEAM END ANCHOR | |
| 0160 | 606061 | 838.000 | L.F. | DRAINAGE STRUCTURE PROTECTION SYSTEM | |
| 0170 | 606610 | 17,040.000 | L.F. | TEMPORARY CWB RETAINED BY THE CONTRACTOR | |
| 0180 | 606619 | 17,040.000 | L.F. | RESETTING OF CONCRETE WALL BARRIER | |
| 0190 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0200 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0210 | 622002 | 1.000 | EACH | FIELD LABORATORY, TYPE II | |
| 0220 | 622110 | 1.000 | EACH | SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY | |
| 0230 | 630100 | 17,040.000 | L.F. | MULTIPLE GLARE SHIELDING | |
| 0240 | 631000 | 64,000.000 | L.F. | RUMBLE STRIPS | |
| 0250 | 632000 | 1.600 | ACRE | CLASS A SEEDING | |
| 0260 | 702610 | 2.000 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0270 | 702810 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR CONSTRUCTION | |
| 0280 | 704701 | 72,000.000 | L.F. | HOT THERMOPLASTIC PAVEMENT MARKINGS 6" | |
| 0290 | 720100 | 2.000 | EACH | SAND BARREL VEHICULAR IMPACT ATTENUATOR | |

UNIT

| | | |
|-------------------|---|---------------|
| 0300 720110 2.000 | EACH REMOVE/RESET IMPACT ATTENUATOR UNIT | |
| 0310 801000 1.000 | LS CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0320 802000 1.000 | LS POST CONSTRUCTION PLANS | \$5,000.00000 |
| 0330 901000 1.000 | LS CONTRACTOR PROCESS QUALITY CONTROL | |

(33 Items)

Proposal 5100900

Roadway Rehabilitation

Proposal information table

Date Generated: 09/21/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 003 Highway Number:
Items: 23 Counties: Torrance
Project ID: 5100900

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-------------|------|--|-------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 203100 | 1,630.000 | C.Y. | BORROW | |
| 0020 | 403701 | 620.000 | TON | OPEN GRADED FRICTION COURSE COMPLETE | |
| 0030 | 405000 | 3,000.000 | S.Y. | DETOUR PAVEMENT CONSTRUCTION | |
| 0040 | 407000 | 10.000 | TON | ASPHALT MATERIAL FOR TACK COAT | |
| 0050 | 414000 | 411,200.000 | SYIN | COLD MILLING (ASPHALT) | |
| 0060 | 423282 | 4,420.000 | TON | HMA SP-III COMPLETE | |
| 0070 | 450200 | 82,200.000 | S.Y. | THIN CONCRETE BONDED OVERLAY-6" | |
| 0080 | 450205 | 1,096.000 | C.Y. | FURNISH ADDITIONAL CONCRETE PAVING MATERIAL | |
| 0090 | 452000 | 229,000.000 | L.F. | SEALING CONCRETE PAVEMENT JOINTS | |
| 0100 | 570024 | 1,480.000 | L.F. | 24" CULVERT PIPE | |
| 0110 | 603281 | 1.000 | LS | SWPPP PLAN PREPARATION AND MAINTENANCE | |
| 0120 | 606610 | 29,200.000 | L.F. | TEMPORARY CWB RETAINED BY THE CONTRACTOR | |
| 0130 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0140 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0150 | 622002 | 1.000 | EACH | FIELD LABORATORY, TYPE II | |
| 0160 | 622100 | 1.000 | EACH | SUPPLEMENTAL FIELD LABORATORY | |
| 0170 | 631000 | 56,000.000 | L.F. | RUMBLE STRIPS | |
| 0180 | 702610 | 2.000 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0190 | 702810 | 1.000 | LS | TRAFFIC CONTROL DEVICES FOR CONSTRUCTION | |
| 0200 | 704000 | 275,700.000 | L.F. | RETROREFLECTORIZED PAINTED MARKINGS 4" | |
| 0210 | 720100 | 3.000 | EACH | SAND BARREL VEHICULAR IMPACT ATTENUATOR UNIT | |
| 0220 | 801000 | 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0230 | 901000 | 1.000 | LS | CONTRACTOR PROCESS QUALITY CONTROL | |

(23 Items)

Proposal 5100930

Roadway Rehabilitation

Proposal information table

Date Generated: 09/21/2016 Sections: 1
Date Revised: Amendments: 0
Call Order: 004 Highway Number:
Items: 29 Counties: San Juan
Project ID: 5100930

Proposal items table

| Line | Item | Quantity | Unit | Description | Price |
|------------------------------|--------|-------------|------|---|-------|
| Section 0001: ROADWAY | | | | | |
| 0010 | 203211 | 1,400.000 | S.Y. | UNSTABLE SUBGRADE STABILIZATION | |
| 0020 | 207000 | 26,300.000 | S.Y. | SUBGRADE PREPARATION | |
| 0030 | 303000 | 8,300.000 | TON | BASE COURSE | |
| 0040 | 403701 | 2,790.000 | TON | OPEN GRADED FRICTION COURSE COMPLETE | |
| 0050 | 407000 | 50.000 | TON | ASPHALT MATERIAL FOR TACK COAT | |
| 0060 | 408100 | 50.000 | TON | PRIME COAT MATERIAL | |
| 0070 | 414000 | 123,500.000 | SYIN | COLD MILLING (ASPHALT) | |
| 0080 | 423282 | 30,600.000 | TON | HMA SP-III COMPLETE | |
| 0090 | 601000 | 1.000 | LS | REMOVAL OF STRUCTURES AND OBSTRUCTIONS | |
| 0100 | 601110 | 26,300.000 | S.Y. | REMOVAL OF SURFACING | |
| 0110 | 613000 | 1.000 | LS | CLEANING CULVERTS AND DRAINAGE STRUCTURES | |
| 0120 | 618000 | 1.000 | LS | TRAFFIC CONTROL MANAGEMENT | |
| 0130 | 621000 | 1.000 | LS | MOBILIZATION | |
| 0140 | 622002 | 1.000 | EACH | FIELD LABORATORY, TYPE II | |
| 0150 | 622110 | 1.000 | EACH | SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY | |
| 0160 | 631000 | 60,900.000 | L.F. | RUMBLE STRIPS | |
| 0170 | 701000 | 540.000 | S.F. | PANEL SIGNS | |
| 0180 | 701100 | 135.000 | L.F. | STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS | |
| 0190 | 702000 | 640.000 | S.F. | CONSTRUCTION SIGNING | |
| 0200 | 702100 | 500.000 | L.F. | STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING | |
| 0210 | 702110 | 16.000 | EACH | PORTABLE SIGN SUPPORT | |
| 0220 | 702238 | 2.000 | EACH | BARRICADE, TYPE III-8' | |
| 0230 | 702320 | 98.000 | EACH | VERTICAL PANEL, TYPE BACK TO BACK | |
| 0240 | 702525 | 12.000 | EACH | CHANNELIZATION DEVICES TYPE DRUM | |
| 0250 | 702610 | 2.000 | EACH | PORTABLE CHANGEABLE MESSAGE SIGN | |
| 0260 | 703205 | 48.000 | EACH | TUBULAR FLEXIBLE TRAFFIC MARKER | |
| 0270 | 704000 | 190,100.000 | L.F. | RETROREFLECTORIZED PAINTED MARKINGS 4" | |
| 0280 | 801000 | 1.000 | LS | CONSTRUCTION STAKING BY THE CONTRACTOR | |
| 0290 | 901000 | 1.000 | LS | CONTRACTOR PROCESS QUALITY CONTROL | |

(29 Items)