

Proposal A300699

Bridge Rehabilitation

Proposal information table

Date Generated: 12/22/2016

Sections: 2

Date Revised:

Amendments: 0

Call Order: 001

Highway Number:

Items: 12

Counties: Bernalillo

Project ID: A300699

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	530300	90.000	LB	REPLACEMENT REINFORCING BARS GRADE 60	
0020	533000	15.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0030	536001	21,185.000	S.Y.	EPOXY URETHANE POLYMER CONCRETE BRIDGE DECK OVERLAY	
Section 0002: ROADWAY					
0040	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0050	618012	1.000	DAY	PUBLIC AWARENESS	

0060	621000	1.000	LS	MOBILIZATION	
0070	702610	8.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0080	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0090	702850	1.000	ALOW	LAW ENFORCEMENT IN CONSTRUCTION ZONE	\$20,000.00000
0100	704701	9,000.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0110	704876	730.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
0120	704877	190.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TH	
(12 Items)					

Proposal LC00140

Signalization, Roadway Reconstruction

Proposal information table

Date Generated: 12/22/2016

Sections: 1

Date Revised:

Amendments: 0

Call Order: 002

Highway Number:

Items: 95

Counties: Dona Ana

Project ID: LC00140

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	100.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	40.000	C.Y.	BORROW	
0040	203211	700.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0050	207000	700.000	S.Y.	SUBGRADE PREPARATION	
0060	303015	700.000	S.Y.	BASE COURSE	

0070	416000	700.000	S.Y.	MINOR PAVEMENT	
0080	502036	32.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0090	502042	16.000	L.F.	DRILLED SHAFT FOUNDATION 42" DIAMETER	
0100	502048	16.000	L.F.	DRILLED SHAFT FOUNDATION 48" DIAMETER	
0110	511000	10.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0120	511200	60.000	S.Y.	STRUCTURAL CONCRETE, CLASS A-4"	
0130	540060	4,065.000	LB	REINFORCING BARS GRADE 60	
0140	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0150	601110	990.000	S.Y.	REMOVAL OF SURFACING	
0160	607079	190.000	L.F.	PEDESTRIAN/BICYCLE RAILING	
0170	608004	230.000	S.Y.	CONCRETE SIDEWALK 4"	
0180	608404	130.000	S.Y.	CONCRETE MEDIAN PAVEMENT 4" (COLORED AND PATTERNED)	
0190	609450	450.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 8" X 30"	
0200	609478	340.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	
0210	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	

0220	617003	1.000	LS	VIDEO TAPING	
0230	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0240	618011	1.000	LS	PUBLIC AWARENESS	\$3,500.00000
0250	621000	1.000	LS	MOBILIZATION	
0260	623331	1.000	EACH	CURB DROP INLET TYPE I-B, OVER 4'	
0270	663049	1.000	LS	PRECONSTRUCTION UTILITY SURVEY	
0280	663866	2.000	EACH	REMOVE AND REPLACE WATER METER	
0290	664995	1.000	LS	IRRIGATION SYSTEM	
0300	667110	3.000	EACH	MAIL BOX INSTALLATION-SINGLE	
0310	701000	55.000	S.F.	PANEL SIGNS	
0320	701100	60.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0330	702000	500.000	S.F.	CONSTRUCTION SIGNING	
0340	702100	750.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0350	702110	20.000	EACH	PORTABLE SIGN SUPPORT	
0360	702238	3.000	EACH	BARRICADE, TYPE III-8'	

0370	702525	50.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0380	702600	2.000	EACH	SEQUENTIAL ARROW DISPLAY	
0390	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0400	702811	1.000	LS	TRAFFIC CONTROL DEVICES FOR PEDESTRIAN AND BICYCLIST	
0410	704000	12,400.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0420	704099	700.000	L.F.	TEMPORARY STRIPING	
0430	704704	550.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKING 24"	
0440	704717	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0450	704718	6.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0460	704720	4.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0470	704732	4.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING BIKE SYMBOL (BIKEWAY)	
0480	705000	1.000	ALOW	SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$5,000.00000
0490	706000	1.000	EACH	SERVICE POLE (SIGNAL)	
0500	706100	1.000	EACH	SERVICE RISER (SIGNAL)	
0510	706200	1.000	EACH	METER PEDESTAL (SIGNAL)	

0520	706350	1.000	LS	POWER SERVICE INSTALLATION	\$15,000.00000
0530	707010	1.000	EACH	TYPE I STANDARD, 10'	
0540	707013	2.000	EACH	TYPE I STANDARD, 13'	
0550	707015	2.000	EACH	TYPE I STANDARD, 15'	
0560	707320	1.000	EACH	TYPE III STANDARD, 20' ARM	
0570	707325	1.000	EACH	TYPE III STANDARD, 25' ARM	
0580	707350	1.000	EACH	TYPE III STANDARD, 50' ARM	
0590	707355	1.000	EACH	TYPE III STANDARD, 55' ARM	
0600	707810	1.000	EACH	REMOVE & RESET LIGHTING STANDARD & LUMINAIRE	
0610	709020	705.000	L.F.	RIGID ELECTRICAL CONDUIT 2" (DIA.)	
0620	709030	1,165.000	L.F.	RIGID ELECTRICAL CONDUIT 3" (DIA.)	
0630	709040	85.000	L.F.	RIGID ELECTRICAL CONDUIT 4" (DIA.)	
0640	710000	4.000	EACH	ELECTRICAL PULL BOX (STANDARD)	
0650	710010	8.000	EACH	ELECTRICAL PULL BOX (LARGE)	
0660	711005	1,990.000	L.F.	MULTI CONDUCTOR CABLE 5	
0670	711007	330.000	L.F.	MULTI CONDUCTOR CABLE 7	

0680	711020	1,180.000	L.F.	MULTI CONDUCTOR CABLE 20	
0690	711102	1,115.000	L.F.	SINGLE CONDUCTOR 2	
0700	711106	855.000	L.F.	SINGLE CONDUCTOR 6	
0710	711108	1,760.000	L.F.	SINGLE CONDUCTOR 8	
0720	711110	1,520.000	L.F.	SINGLE CONDUCTOR 10	
0730	712031	11.000	EACH	3 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
0740	712041	6.000	EACH	4 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
0750	712202	8.000	EACH	PEDESTRIAN COUNTDOWN SIGNAL (LED)	
0760	712330	6.000	EACH	3 SECTION BACKPLATE	
0770	712340	3.000	EACH	4 SECTION BACKPLATE	
0780	713025	8.000	EACH	ACCESSIBLE PEDESTRIAN SIGNAL PUSH BUTTON STATION	
0790	713030	145.000	L.F.	LOOP DETECTOR WIRE	
0800	713420	1.000	EACH	PHASE SELECTOR RACK, 2 CHANNEL	
0810	713430	2.000	EACH	PHASE SELECTOR MODULE	
0820	713511	3.000	EACH	OPTICAL DETECTOR, 1 DIRECTION, 1 CHANNEL	
0830	713600	580.000	L.F.	OPTICAL DETECTOR CABLE	

0840	713807	860.000	L.F.	VIDEO CABLE	
0850	713810	4.000	EACH	VIDEO CAMERA	
0860	714000	1.000	EACH	TRAFFIC ACTUATED CONTROLLER	
0870	714280	1.000	EACH	8 PHASE DOUBLE RING CONTROLLER CABINET	
0880	714300	1.000	LS	CLOSED LOOP TRAFFIC CONTROL SYSTEM	
0890	716301	4.000	EACH	INTERNALLY ILLUMINATED SIGN	
0900	716700	4.000	EACH	LUMINAIRE TYPE LED	
0910	721000	3,200.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0920	721101	5.000	EACH	REMOVAL OF PAVEMENT MARKING	
0930	750000	1.000	LS	INTELLIGENT TRANSPORTATION SYSTEM	
0940	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0950	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
(95 Items)					

Proposal E100210

Roadway Reconstruction

Proposal information table

Date Generated: 12/22/2016

Sections: 1

Date Revised:

Amendments: 0

Call Order: 003

Highway Number:

Items: 31

Counties: Dona Ana

Project ID: E100210

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	203000	850.000	C.Y.	UNCLASSIFIED EXCAVATION	
0020	207000	1,559.000	S.Y.	SUBGRADE PREPARATION	
0030	303000	446.000	TON	BASE COURSE	
0040	416000	1,213.000	S.Y.	MINOR PAVEMENT	
0050	417000	356.000	S.Y.	MISCELLANEOUS PAVING	
0060	417100	246.000	L.F.	ASPHALT CURB	

0070	511200	123.000	S.Y.	STRUCTURAL CONCRETE, CLASS A-4"	
0080	515000	95.000	C.Y.	REINF.CONCRETE FOR MINOR STRUCTURES	
0090	570473	286.000	L.F.	48" STORM DRAIN CULVERT PIPE	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0110	601110	409.000	S.Y.	REMOVAL OF SURFACING	
0120	602010	80.000	C.Y.	RIPRAP CLASS B	
0130	606001	662.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0140	606051	2.000	EACH	END TREATMENT TL-3 END TERMINAL	
0150	606053	2.000	EACH	END TREATMENT W-BEAM END ANCHOR	
0160	606610	600.000	L.F.	TEMPORARY CWB RETAINED BY THE CONTRACTOR	
0170	606619	420.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	
0180	607004	189.000	L.F.	BARBED WIRE FENCE 4'	
0190	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0200	621000	1.000	LS	MOBILIZATION	
0210	702000	817.000	S.F.	CONSTRUCTION SIGNING	
0220	702100	279.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	

0230	702110	27.000	EACH	PORTABLE SIGN SUPPORT	
0240	702238	8.000	EACH	BARRICADE, TYPE III-8'	
0250	702525	96.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0260	702600	2.000	EACH	SEQUENTIAL ARROW DISPLAY	
0270	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0280	703003	2.000	EACH	OBJECT MARKER TYPE 3	
0290	704000	11,550.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0300	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0310	802000	1.000	LS	POST CONSTRUCTION PLANS	\$5,000.00000
(31 Items)					

Proposal 61009106100911

Roadway Reconstruction, Bridge Replacement

Proposal information table

Date
Generated: 12/22/2016

Sections: 2

Date
Revised:

Amendments: 0

Call Order: 004

Highway
Number:

Items: 109

Counties: Valencia Cibola

Project ID: 6100910

Proposal items table

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	73,065.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	56,270.000	C.Y.	BORROW	
0040	203211	47,150.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	
0050	203301	22,700.000	C.Y.	ROCK EXCAVATION	
0060	207000	435,430.000	S.Y.	SUBGRADE PREPARATION	

0070	210000	25.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0080	301013	470,750.000	S.Y.	COLD CENTRAL PLANT RECYCLE-FOAMED ASPHALT STABILIZED BASE	
0090	301014	1,792.000	TON	ASPHALT BINDER	
0100	301015	1,077.000	TON	MINERAL FILLER	
0110	303000	119,000.000	TON	BASE COURSE	
0120	403701	8,760.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0130	405000	58,100.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0140	407000	365.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0150	408100	826.000	TON	PRIME COAT MATERIAL	
0160	414000	247,400.000	SYIN	COLD MILLING (ASPHALT)	
0170	417000	4,500.000	S.Y.	MISCELLANEOUS PAVING	
0180	423282	83,820.000	TON	HMA SP-III COMPLETE	
0190	423283	44,060.000	TON	HMA SP-IV COMPLETE	
0200	502036	80.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0210	505001	4.000	EACH	CROSSHOLE SONIC LOGGING DEPARTMENT TESTING	
0220	505010	2.000	EACH	LOW STRAIN INTEGRITY DEPARTMENT TESTING	

0230	511000	245.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0240	511030	460.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0250	511300	41.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
0260	511352	15,700.000	LB	REUSABLE TEMPORARY BRIDGE ADDITIONAL COMPONENTS	
0270	511355	1.000	EACH	REUSABLE TEMPORARY BRIDGE ERECTION	
0280	511360	1.000	EACH	REUSABLE TEMPORARY BRIDGE DISMANTLING	
0290	519001	530.000	S.Y.	NON STRUCTURAL SHOTCRETE	
0300	540060	80,370.000	LB	REINFORCING BARS GRADE 60	
0310	541200	4,250.000	LB	STRUCTURAL STEEL FOR MISCELLANEOUS STRUCTURES	
0320	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0330	570024	2,622.000	L.F.	24" CULVERT PIPE	
0340	570025	4.000	EACH	24" CULVERT PIPE END SECTION	
0350	570030	796.000	L.F.	30" CULVERT PIPE	
0360	570036	1,229.000	L.F.	36" CULVERT PIPE	
0370	570042	32.000	L.F.	42" CULVERT PIPE	
0380	570054	82.000	L.F.	54" CULVERT PIPE	

0390	570060	540.000	L.F.	60" CULVERT PIPE	
0400	570156	352.000	L.F.	28" SX20" R (NOMINAL) CULVERT PIPE ARCH	
0410	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0420	601110	179,910.000	S.Y.	REMOVAL OF SURFACING	
0430	602000	220.000	C.Y.	RIPRAP CLASS A	
0440	603100	111.000	ACRE	TEMPORARY SOIL STABILANT	
0450	603221	710.000	L.F.	CHECK DAM TYPE II	
0460	603261	8,900.000	L.F.	MULCH SOCKS	
0470	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0480	606001	5,825.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0490	606051	34.000	EACH	END TREATMENT TL-3 END TERMINAL	
0500	606061	188.000	L.F.	DRAINAGE STRUCTURE PROTECTION SYSTEM	
0510	606062	14.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0520	606542	368.000	L.F.	CONCRETE WALL BARRIER 42"	
0530	606600	2,200.000	L.F.	TEMPORARY CWB RETAINED BY THE DEPARTMENT	
0540	606619	2,000.000	L.F.	RESETTING OF CONCRETE WALL BARRIER	

0550	607004	74,840.000	L.F.	BARBED WIRE FENCE 4'	
0560	607220	20.000	L.F.	REMOVE AND REBUILD CHAIN LINK FENCE	
0570	607250	2.000	EACH	REMOVE AND RESET CHAIN LINK GATE	
0580	607251	5.000	EACH	REMOVE AND RESET GATE	
0590	607916	9.000	EACH	BARBED WIRE GATE 16'	
0600	610042	1.000	EACH	CATTLE GUARD 42'	
0610	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0620	618011	1.000	LS	PUBLIC AWARENESS	
0630	621000	1.000	LS	MOBILIZATION	
0640	622002	1.000	EACH	FIELD LABORATORY, TYPE II	
0650	622100	1.000	EACH	SUPPLEMENTAL FIELD LABORATORY	
0660	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	
0670	622200	1.000	EACH	FIELD OFFICE	
0680	623012	2.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=3'1" TO 6'0"	
0690	631000	192,380.000	L.F.	RUMBLE STRIPS	
0700	632000	84.000	ACRE	CLASS A SEEDING	

0710	632020	9.000	ACRE	CLASS C SEEDING	
0720	701000	1,210.000	S.F.	PANEL SIGNS	
0730	701100	2,530.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0740	702610	4.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0750	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0760	703002	60.000	EACH	OBJECT MARKER TYPE 2	
0770	703003	3.000	EACH	OBJECT MARKER TYPE 3	
0780	704000	464,500.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0790	704700	292,300.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"	
0800	704718	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0810	704720	1.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0820	720060	7.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0830	721000	80,200.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0840	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0850	802000	1.000	LS	POST CONSTRUCTION PLANS	\$40,000.00000

0860	901000	1.000	LS	CONTRACTOR PROCESS QUALITY CONTROL	
Section 0002: BRIDGE					
0870	203000	8,530.000	C.Y.	UNCLASSIFIED EXCAVATION	
0880	210000	2,770.000	C.Y.	EXCAVATION AND BACKFILL FOR MAJOR STRUCTURES	
0890	502036	133.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0900	502042	66.000	L.F.	DRILLED SHAFT FOUNDATION 42" DIAMETER	
0910	502148	30.000	L.F.	PERMANENT CASING 48" DIAMETER	
0920	502600	15.000	L.F.	OBSTRUCTION REMOVAL	
0930	505001	9.000	EACH	CROSSHOLE SONIC LOGGING DEPARTMENT TESTING	
0940	505010	2.000	EACH	LOW STRAIN INTEGRITY DEPARTMENT TESTING	
0950	511030	2,510.000	C.Y.	STRUCTURAL CONCRETE, CLASS AA	
0960	511300	90.000	C.Y.	SUBSTRUCTURE CONCRETE CLASS A	
0970	512003	316.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0980	514042	420.000	L.F.	CONCRETE BARRIER RAILINGS 42"	
0990	518045	874.000	L.F.	PRESTRESSED CONCRETE BRIDGE MEMBER TYPE 45	
1000	531001	4,000.000	S.F.	PERMANENT ANTI-GRAFFITI PROTECTIVE COATING	

1010	535100	890.000	S.Y.	CONCRETE SURFACE TREATMENT	
1020	540060	498,080.000	LB	REINFORCING BARS GRADE 60	
1030	540160	68,830.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
1040	541000	3,268.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
1050	562000	85.000	L.F.	BRIDGE JOINT STRIP SEAL	
1060	564000	100.000	L.F.	PREFORMED CLOSED CELL FOAM BRIDGE JOINT SEALS	
1070	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
1080	602000	1,310.000	C.Y.	RIPRAP CLASS A	
1090	602030	450.000	C.Y.	RIPRAP CLASS D	
(109 Items)					