

Proposal 5100650R3

Roadway Reconstruction/Rehab, Lighting, Signalization

Call Order: 001

Items: 129 County: Los Alamos

Project ID: 5100650R3

Line	Item	Quantity	Unit	Description	Price
Section 0001: ROADWAY					
0010	201000	1.000	LS	CLEARING AND GRUBBING	
0020	203000	11,000.000	C.Y.	UNCLASSIFIED EXCAVATION	
0030	203100	100.000	C.Y.	BORROW	
0040	203301	110.000	C.Y.	ROCK EXCAVATION	
0050	206100	200.000	C.Y.	SELECT BACKFILL MATERIAL	
0060	207000	24,200.000	S.Y.	SUBGRADE PREPARATION	
0070	210002	1,230.000	C.Y.	MAJOR STRUCTURE EXCAVATION	
0080	210003	460.000	C.Y.	MAJOR STRUCTURE BACKFILL	
0090	303000	7,230.000	TON	BASE COURSE	
0100	405000	7,300.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0110	408100	43.000	TON	PRIME COAT MATERIAL	
0120	414155	8,400.000	S.Y.	COLD MILLING (ASPHALT) 5 1/2"	
0130	417100	70.000	L.F.	ASPHALT CURB	
0140	423282	5,820.000	TON	HMA SP-III COMPLETE	
0150	423283	2,960.000	TON	HMA SP-IV COMPLETE	
0160	451080	1,650.000	S.Y.	CONCRETE PAVEMENT-8"	
0170	502030	345.000	L.F.	DRILLED SHAFT FOUNDATION 30" DIAMETER	
0180	502036	80.000	L.F.	DRILLED SHAFT FOUNDATION 36" DIAMETER	
0190	511000	530.000	C.Y.	STRUCTURAL CONCRETE, CLASS A	
0200	540060	62,100.000	LB	REINFORCING BARS GRADE 60	
0210	570425	480.000	L.F.	18" STORM DRAIN CULVERT PIPE	
0220	570437	1,460.000	L.F.	24" STORM DRAIN CULVERT PIPE	
0230	570461	470.000	L.F.	36" STORM DRAIN CULVERT PIPE	
0240	570473	170.000	L.F.	48" STORM DRAIN CULVERT PIPE	
0250	570479	600.000	L.F.	54" STORM DRAIN CULVERT PIPE	
0260	570484	1.000	EACH	54" STORM DRAIN CULVERT PIPE END SECTION	
0270	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0280	603261	800.000	L.F.	MULCH SOCKS	
0290	603281	1.000	LS	SWPPP PLAN PREPARATION AND	

MAINTENANCE

0300	604002	21,020.000	S.Y.	GEOTEXTILE CLASS 2	
0310	604310	21,020.000	S.Y.	GEOGRID BASE REINFORCEMENT	
0320	606610	600.000	L.F.	TCWB RETAINED BY THE CONTRACTOR (10')	
0330	606619	2,700.000	L.F.	RESETTING OF TCWB (10')	
0340	607079	1,340.000	L.F.	PEDESTRIAN/BICYCLE RAILING	
0350	608004	5,720.000	S.Y.	CONCRETE SIDEWALK 4"	
0360	608006	30.000	S.Y.	CONCRETE SIDEWALK 6"	
0370	608106	630.000	S.Y.	DRIVE PAD 6"	
0380	608404	650.000	S.Y.	CONCRETE MEDIAN PAVEMENT 4" (COLORED AND PATTERNED)	
0390	608406	40.000	S.Y.	CONCRETE MEDIAN PAVEMENT 6" (COLORED AND PATTERNED)	
0400	609109	720.000	L.F.	PINNED CURB	
0410	609324	40.000	L.F.	CONCRETE SLOPED CURB AND GUTTER 6" X 24"	
0420	609380	520.000	L.F.	CONCRETE SLOPED CURB AND GUTTER 8" X 30"	
0430	609424	5,460.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 24"	
0440	609430	3,790.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 6" X 30"	
0450	609450	940.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE B 8" X 30"	
0460	609478	3,070.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 6" X 18"	
0470	609488	200.000	L.F.	CONCRETE VERTICAL CURB AND GUTTER TYPE D 8" X 18"	
0480	609636	320.000	L.F.	CONCRETE VALLEY GUTTER 6" X 36"	
0490	617000	1.000	LS	VIBRATION MONITORING	
0500	617003	1.000	LS	VIDEO TAPING	
0510	617004	1.000	LS	VIBRATION RISK SURVEY	
0520	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0530	618011	1.000	LS	PUBLIC AWARENESS	\$20,000.00000
0540	621000	1.000	LS	MOBILIZATION	
0550	622002	1.000	EACH	FIELD LABORATORY, TYPE II	
0560	622100	1.000	EACH	SUPPLEMENTAL FIELD LABORATORY	
0570	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	
0580	622200	1.000	EACH	FIELD OFFICE	
0590	623000	1.000	EACH	MEDIAN DROP INLET TYPE I (URBAN) H=0'0" TO 3'0"	
0600	623300	1.000	EACH	CURB DROP INLET	
0610	623311	3.000	EACH	CURB DROP INLET TYPE I-B, 0' TO 4'	

0620	623312	8.000	EACH	CURB DROP INLET TYPE II-B, 0' TO 4'
0630	623331	4.000	EACH	CURB DROP INLET TYPE I-B, OVER 4'
0640	623332	11.000	EACH	CURB DROP INLET TYPE II-B, OVER 4'
0650	662000	7.000	EACH	MANHOLE TYPE C-4' DIAMETER 0' TO 6' DEPTH
0660	662010	2.000	EACH	MANHOLE TYPE C-6' DIAMETER 0' TO 6' DEPTH
0670	662042	1.000	EACH	MANHOLE TYPE C-8' DIAMETER OVER 6' TO 10' DEPTH
0680	662044	2.000	EACH	MANHOLE TYPE C-8' DIAMETER OVER 10' TO 14' DEPTH
0690	662072	7.000	EACH	MANHOLE TYPE E-6' DIAMETER OVER 6' TO 10' DEPTH
0700	662074	1.000	EACH	MANHOLE TYPE E-6' DIAMETER OVER 10' TO 14' DEPTH
0710	662400	20.000	EACH	MANHOLE ADJUSTMENT
0720	663202	1.000	LS	GAS SYSTEM
0730	663206	1.000	LS	WATER SYSTEM
0740	663207	1.000	LS	SEWER SYSTEM
0750	663208	1.000	LS	FIBER OPTIC SYSTEM
0760	663210	1.000	LS	ELECTRICAL SYSTEM
0770	664000	1.000	LS	LANDSCAPE, COMPLETE
0780	664995	1.000	LS	IRRIGATION SYSTEM
0790	667219	3,200.000	S.F.	GRAVITY WALL
0800	701000	830.000	S.F.	PANEL SIGNS
0810	701031	14.000	EACH	REMOVE AND RESET TRAFFIC SIGN
0820	701100	1,440.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS
0830	701101	56.000	EACH	MULTI-DIRECTIONAL SLIP BASE POSTS FOR ALUMINUM PANEL SIGNS
0840	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN
0850	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION
0860	702811	1.000	LS	TRAFFIC CONTROL DEVICES FOR PEDESTRIAN AND BICYCLIST
0870	703002	12.000	EACH	OBJECT MARKER TYPE 2
0880	704000	53,800.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"
0890	704099	29,300.000	L.F.	TEMPORARY STRIPING
0900	704700	6,470.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 4"
0910	704715	2.000	EACH	HOT THERMOPLASTIC PAVEMENT MARKING COMBINATION (THRU AND RIGHT) ARROW
0920	704716	3.000	EACH	HOT THERMOPLASTIC PAVEMENT

			MARKING COMBINATION (THRU AND LEFT) ARROW	
0930	704717	6.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING RIGHT ARROW	
0940	704718	35.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING LEFT ARROW	
0950	704719	6.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING THRU ARROW	
0960	704720	11.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING WORD (ONLY)	
0970	704728	90.000	L.F. HOT THERMOPLASTIC PAVEMENT MARKING YIELD LINE	
0980	704732	14.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING BIKE SYMBOL (BIKEWAY)	
0990	704733	1.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING HANDICAPPED SYMBOL	
1000	704735	3.000	EACH HOT THERMOPLASTIC PAVEMENT MARKING RIGHT LANE DROP ARROW	
1010	705000	1.000	ALLOW SIGNAL/LIGHTING SYSTEM START-UP COSTS	\$5,000.00000
1020	706200	1.000	EACH METER PEDESTAL (SIGNAL)	
1030	706350	1.000	LS POWER SERVICE INSTALLATION	\$20,000.00000
1040	706405	1.000	EACH LIGHTING CONTROL CABINET-SIX CIRCUIT	
1050	706420	3.000	EACH LIGHTING CONTROL CABINET-TWO CIRCUIT	
1060	707004	4.000	EACH TYPE I STANDARD, 4'	
1070	707018	4.000	EACH TYPE I STANDARD, 18'	
1080	707220	4.000	EACH TYPE II STANDARD, 20' ARM	
1090	707530	52.000	EACH TYPE V STANDARD, 30'	
1100	707740	4.000	EACH TYPE V STANDARD, 30', 2 ARMS	
1110	707801	1.000	EACH REMOVE & RESET TYPE I STANDARD COMPLETE	
1120	709020	6,365.000	L.F. RIGID ELECTRICAL CONDUIT 2" (DIA.)	
1130	709030	1,240.000	L.F. RIGID ELECTRICAL CONDUIT 3" (DIA.)	
1140	710000	10.000	EACH ELECTRICAL PULL BOX (STANDARD)	
1150	711005	350.000	L.F. MULTI CONDUCTOR CABLE 5	
1160	711007	980.000	L.F. MULTI CONDUCTOR CABLE 7	
1170	711102	16,080.000	L.F. SINGLE CONDUCTOR 2	
1180	711230	375.000	L.F. SINGLE CONDUCTOR 3/0	
1190	712011	16.000	EACH 1 SECTION TRAFFIC SIGNAL ASSEMBLY (LED)	
1200	713025	4.000	EACH ACCESSIBLE PEDESTRIAN SIGNAL PUSH BUTTON STATION	
1210	714000	2.000	EACH TRAFFIC ACTUATED CONTROLLER	
1220	714240	2.000	EACH 4 PHASE SINGLE RING CONTROLLER	

			CABINET	
1230	716701	60.000	EACH LED ROADWAY LUMINAIRE	
1240	720060	2.000	EACH VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
1250	720100	2.000	EACH SAND BARREL VEHICULAR IMPACT ATTENUATOR UNIT	
1260	720110	12.000	EACH REMOVE/RESET IMPACT ATTENUATOR UNIT	
1270	721000	110.000	L.F. REMOVAL OF PAVEMENT STRIPE	
1280	801000	1.000	LS CONSTRUCTION STAKING BY THE CONTRACTOR	
1290	802000	1.000	LS POST CONSTRUCTION PLANS	\$10,000.00000

(129 Items)

Proposal 6100833

Bridge Rehabilitation, Roadway Reconstruction

Call Order: 002

Items: 82 County: Cibola

Project ID: 6100833

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	210001	100.000	C.Y.	UNSUITABLE MATERIAL EXCAVATION	
0020	210002	1,000.000	C.Y.	MAJOR STRUCTURE EXCAVATION	
0030	210003	620.000	C.Y.	MAJOR STRUCTURE BACKFILL	
0040	512003	640.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0050	529000	1.000	LS	PIER AND ABUTMENT BEARING MODIFICATIONS	
0060	532000	280.000	S.Y.	PENETRATING WATER REPELLENT TREATMENT	
0070	533000	20.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0080	533003	200.000	LB	REPLACEMENT REINFORCING BARS	
0090	534000	10.000	GAL	EPOXY INJECTION, TYPE I	
0100	535100	2,200.000	S.Y.	CONCRETE SURFACE TREATMENT	
0110	540160	155,000.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0120	541000	18,000.000	LB	STRUCTURAL STEEL FOR CONCRETE BRIDGES	
0130	543002	830.000	L.F.	METAL RAILING, TYPE A42	
0140	546000	1.000	LS	RECOATING STRUCTURES	
0150	546200	570.000	S.F.	SP 3 POWER TOOL CLEANING	
0160	546210	570.000	S.F.	SP 11 POWER TOOL CLEANING	
0170	562000	190.000	L.F.	BRIDGE JOINT STRIP SEAL	
0180	563100	720.000	L.F.	POLYMER BRIDGE JOINT SEALS, TYPE A	
0190	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0200	602000	600.000	C.Y.	RIPRAP CLASS A	
0210	604002	1,000.000	S.Y.	GEOTEXTILE CLASS 2	
0220	604300	3,000.000	S.Y.	GEOGRID REINFORCEMENT	
Section 0002: ROADWAY					
0230	201000	1.000	LS	CLEARING AND GRUBBING	
0240	203000	1,000.000	C.Y.	UNCLASSIFIED EXCAVATION	
0250	203100	3,800.000	C.Y.	BORROW	
0260	203200	1,200.000	C.Y.	UNSUITABLE MATERIAL EXCAVATION	
0270	203211	2,800.000	S.Y.	UNSTABLE SUBGRADE STABILIZATION	

0280	206000	45.000	C.Y.	UNSUITABLE MATERIAL EXCAVATION	
0290	303000	21,470.000	TON	BASE COURSE	
0300	403701	210.000	TON	OPEN GRADED FRICTION COURSE COMPLETE	
0310	405000	13,800.000	S.Y.	DETOUR PAVEMENT CONSTRUCTION	
0320	407000	8.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0330	407001	30.000	TON	FOG SEAL	
0340	408100	70.000	TON	PRIME COAT MATERIAL	
0350	414000	16,700.000	SYIN	COLD MILLING (ASPHALT)	
0360	416000	12,200.000	S.Y.	MINOR PAVEMENT	
0370	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0380	570030	320.000	L.F.	30" CULVERT PIPE	
0390	570031	2.000	EACH	30" CULVERT PIPE END SECTION	
0400	570032	570.000	L.F.	30" CULVERT PIPE - SLIP LINING	
0410	570084	182.000	L.F.	84" CULVERT PIPE	
0420	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0430	601110	15,200.000	S.Y.	REMOVAL OF SURFACING	
0440	602000	20.000	C.Y.	RIPRAP CLASS A	
0450	603051	1.000	LS	CLEAN WATER ACT COMPLIANCE WORK PLAN	
0460	603100	10.000	ACRE	TEMPORARY SOIL STABILANT	
0470	603262	1,900.000	L.F.	COMPOSTED MULCH SOCKS	
0480	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0490	604002	16,400.000	S.Y.	GEOTEXTILE CLASS 2	
0500	604310	43,100.000	S.Y.	GEOGRID BASE REINFORCEMENT	
0510	606001	1,000.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0520	606051	4.000	EACH	END TREATMENT TL-3 END TERMINAL	
0530	606062	4.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0540	606610	4,340.000	L.F.	TCWB RETAINED BY THE CONTRACTOR (10')	
0550	606619	3,840.000	L.F.	RESETTING OF TCWB (10')	
0560	607004	3,000.000	L.F.	BARBED WIRE FENCE 4'	
0570	607318	1.000	EACH	STANDARD GATE, 18'	
0580	613000	1.000	LS	CLEANING CULVERTS AND DRAINAGE STRUCTURES	
0590	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0600	618011	1.000	LS	PUBLIC AWARENESS	\$4,000.00000
0610	621000	1.000	LS	MOBILIZATION	
0620	622002	1.000	EACH	FIELD LABORATORY, TYPE II	
0630	622110	1.000	EACH	SUPPLEMENTAL HOT-MIX ASPHALT FIELD LABORATORY	

0640	623013	1.000	EACH	MEDIAN DROP INLET TYPE I (RURAL) H=6'1" TO 9'0"	
0650	623093	1.000	EACH	MEDIAN DROP INLET 10'X5' (RURAL) H=0'0" TO 3'0"	
0660	630100	3,880.000	L.F.	MULTIPLE GLARE SHIELDING	
0670	631000	16,000.000	L.F.	RUMBLE STRIPS	
0680	632000	8.000	ACRE	CLASS A SEEDING	
0690	701000	64.000	S.F.	PANEL SIGNS	
0700	701100	84.000	L.F.	STEEL POST AND BASE POST FOR ALUMINUM PANEL SIGNS	
0710	702610	2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0720	702810	1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0730	704099	117,900.000	L.F.	TEMPORARY STRIPING	
0740	704100	1,600.000	L.F.	REMOVABLE MARKING TAPE	
0750	704701	43,500.000	L.F.	HOT THERMOPLASTIC PAVEMENT MARKINGS 6"	
0760	704876	1,040.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TG	
0770	704877	1,040.000	EACH	TEMPORARY REFLECTIVE RAISED PAVEMENT MARKER, TYPE TH	
0780	720060	2.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0790	720110	2.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0800	721000	94,000.000	L.F.	REMOVAL OF PAVEMENT STRIPE	
0810	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0820	802000	1.000	LS	POST CONSTRUCTION PLANS	\$4,000.00000

(82 Items)

Proposal 1101540

Bridge Rehabilitation, Erosion Control

Call Order: 003

Items: 33 County: Socorro

Project ID: 1101540

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	453000	1,000.000	LB	VOID FILLING OR SLAB JACKING AT STRUCTURE GRADE	
0020	533000	50.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0030	533001	225.000	EACH	EMBEDDED GALVANIC ANODES	
0040	533003	200.000	LB	REPLACEMENT REINFORCING BARS	
0050	534000	30.000	GAL	EPOXY INJECTION, TYPE I	
0060	535100	853.000	S.Y.	CONCRETE SURFACE TREATMENT	
0070	546000	1.000	LS	RECOATING STRUCTURES	
0080	546200	907.000	S.F.	SP 3 POWER TOOL CLEANING	
0090	546210	303.000	S.F.	SP 11 POWER TOOL CLEANING	
0100	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
Section 0002: ROADWAY					
0110	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0120	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0130	602000	1,130.000	C.Y.	RIPRAP CLASS A	
0140	602030	1,730.000	C.Y.	RIPRAP CLASS D	
0150	602200	130.000	C.Y.	GABIONS	
0160	603050	1.000	ALOW	CLEAN WATER ACT COMPLIANCE WORK PLAN	\$10,000.00000
0170	603221	80.000	L.F.	CHECK DAM TYPE II	
0180	603262	630.000	L.F.	COMPOSTED MULCH SOCKS	
0190	603281	1.000	LS	SWPPP PLAN PREPARATION AND MAINTENANCE	
0200	606001	50.000	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0210	606051	4.000	EACH	END TREATMENT TL-3 END TERMINAL	
0220	606062	4.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0230	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0240	621000	1.000	LS	MOBILIZATION	
0250	702000	451.000	S.F.	CONSTRUCTION SIGNING	

0260	702100	280.000	L.F.	STEEL POSTS AND BASE POSTS FOR CONSTRUCTION SIGNING	
0270	702110	14.000	EACH	PORTABLE SIGN SUPPORT	
0280	702238	2.000	EACH	BARRICADE, TYPE III-8'	
0290	702525	30.000	EACH	CHANNELIZATION DEVICES TYPE DRUM	
0300	703003	4.000	EACH	OBJECT MARKER TYPE 3	
0310	704000	4,100.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0320	801000	1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0330	802000	1.000	LS	POST CONSTRUCTION PLANS	\$2,500.00000

(33 Items)

Proposal 4101630

Bridge Rehabilitation, Miscellaneous Paving

Call Order: 004

Items: 33 County: Union

Project ID: 4101630

Line	Item	Quantity	Unit	Description	Price
Section 0001: BRIDGE					
0010	512003	5.000	C.Y.	HIGH PERFORMANCE CONCRETE (HPD)	
0020	514042	306.000	L.F.	CONCRETE BARRIER RAILINGS 42"	
0030	516000	5.000	C.Y.	FLOWABLE FILL	
0040	531000	489.000	S.Y.	BRIDGE DECK SEALANT MEMBRANE	
0050	533000	233.000	S.Y.	REPAIR OF CONCRETE STRUCTURES	
0060	540160	650.000	LB	EPOXY COATED REINFORCING BARS GRADE 60	
0070	548002	2,400.000	S.F.	COATING OF CONCRETE - PAINT	
0080	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0090	602000	100.000	C.Y.	RIPRAP CLASS A	
0100	606542	72.000	L.F.	CONCRETE WALL BARRIER 42"	
Section 0002: ROADWAY					
0110	407000	1.000	TON	ASPHALT MATERIAL FOR TACK COAT	
0120	417000	489.000	S.Y.	MISCELLANEOUS PAVING	
0130	547000	1.000	LS	SAFETY AND ENVIRONMENTAL REQUIREMENTS	
0140	601000	1.000	LS	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	
0150	601110	489.000	S.Y.	REMOVAL OF SURFACING	
0160	606001	762.500	L.F.	SINGLE FACE W-BEAM GUARDRAIL	
0170	606051	2.000	EACH	END TREATMENT TL-3 END TERMINAL	
0180	606053	2.000	EACH	END TREATMENT W-BEAM END ANCHOR	
0190	606062	4.000	EACH	TRANSITION METAL BARRIER TO RIGID BARRIER	
0200	606610	460.000	L.F.	TCWB RETAINED BY THE CONTRACTOR (10')	
0210	606619	460.000	L.F.	RESETTING OF TCWB (10')	
0220	618000	1.000	LS	TRAFFIC CONTROL MANAGEMENT	
0230	618011	1.000	LS	PUBLIC AWARENESS	\$2,500.00000
0240	621000	1.000	LS	MOBILIZATION	
0250	701000	42.000	S.F.	PANEL SIGNS	
0260	701100	36.000	L.F.	STEEL POST AND BASE POST FOR	

ALUMINUM PANEL SIGNS

0270 702610 2.000	EACH	PORTABLE CHANGEABLE MESSAGE SIGN	
0280 702810 1.000	LS	TRAFFIC CONTROL DEVICES FOR CONSTRUCTION	
0290 704000 716.000	L.F.	RETROREFLECTORIZED PAINTED MARKINGS 4"	
0300 720060 1.000	EACH	VEHICULAR IMPACT ATTENUATOR UNIT-WORK ZONES	
0310 720110 1.000	EACH	REMOVE/RESET IMPACT ATTENUATOR UNIT	
0320 801000 1.000	LS	CONSTRUCTION STAKING BY THE CONTRACTOR	
0330 802000 1.000	LS	POST CONSTRUCTION PLANS	\$2,500.00000

(33 Items)